BILL OF QUANTITIES

ICF KIT · CONCRETE · LABOUR

2 CASTLE GARDENS, SWANSEA

New 4th-floor storey: 4 flats · 2 Castle Gardens, Swansea SA1 · WALES

Quotation Reference	ES26-055
Project	2 Castle Gardens, Swansea
House Type	New 4th-floor storey only (4 x 2-bed flats) on a steel ring beam over the existing GF-3F masonry building: Nudura 7 courses, 6in XR35 external walls + 6in Standard stair-core / flat-separating walls
Client	Insubloc (Tim Evans) - Nudura distributor
Site Address	2 Castle Gardens, Swansea SA1
BOQ Date	02 November 2026
BOQ Reference	BOQ-ES26-055
Prepared by	Tom Smith — BuildEase Manager, Nudura UK
Issued by	Tremco Construction Products Group
Currency	Pound Sterling (GBP) · VAT at 20%
Measurement Convention	RICS New Rules of Measurement (NRM2)

IMPORTANT NOTICE — DISCLAIMER

- This Bill of Quantities is supplied in good faith based on the BuildEase take-off models for 2 Castle Gardens, Swansea and the ES26-055 Distributor BOM (the distributor sets the ICF material prices).
- ALL QUANTITIES SHOULD BE INDEPENDENTLY CHECKED AND VERIFIED BY THE PROJECT QS / QUANTITY SURVEYOR before tender submission, ordering or contract award.
- This BOQ does NOT include an external render / finish allowance. Any render, coatings or external wall finish must be measured and priced separately.
- Section C (Concrete) volumes are geometric voids — allow ~3% web displacement deduction and ~5% wastage on top when ordering ready-mix.
- Section D (Labour) day estimates are scaled proportionately from a reference project; actual gang productivity will vary with site conditions, weather and trade experience.
- BuildEase, Tremco Construction Products Group and Nudura UK accept no liability for tender or contract outcomes arising from the use of these figures. If in doubt — ask.
- Contact: Tom Smith — BuildEase Manager, Nudura UK — for clarification on any quantity or rate basis in this document.

WALES: the design must satisfy the Building Regulations 2010 as they apply in Wales and the Welsh Government Approved Documents (Approved Documents Wales, incl. Parts L / O 2022 Wales) - building control by Swansea Council (LABC) or a registered building control approver; NOT the English Approved Documents or the Scottish technical handbooks. BUILDING HEIGHT (ADB Diagram D6, to the floor of the top storey): the new 4F FFL is 12,342 above the rear yard (~12.34 m) and ~15.1 m above the LOWEST adjoining ground (front street ASSUMED ~2.8 m below the rear yard - indicative, from the existing elevations; a measured survey must confirm) - the building is IN THE 11-18 m HEIGHT BAND: ALL fire detailing (external-wall materials and the cladding incl. the EPS faces of the ICF, cavity barriers, fire-stopping, compartmentation, the open-air escape stair and every opening onto it) is governed entirely by building control and a fire engineer. Wales: new flats need an automatic fire suppression (sprinkler) system (Building Regulations 2010 reg 37A as applied in Wales / ADB vol 1 Wales) - by others, building control to confirm. 5 storeys with the new 4F on the existing GF-3F masonry: flats = Consequence Class 2B (Approved Document A) - ties / anchorage, the steel ring beam and the transfer steels are engineer-designed (outside the manufacturer tables). The LABC Warranty technical manual caps ICF at 3 storeys unless an independent engineer inspects each pour (pre-pour) and signs off - here the ICF is the top storey of a 5-storey building: the warranty provider must confirm.

DISTRIBUTOR QUOTATION - NOT FOR CONSTRUCTION. Section B carries NO Nudura material prices: the distributor prices the forms, accessories, their delivery and the alignment system; BuildEase prices only the pre-cut service and the pre-cut delivery. The existing building (GF-3F masonry) is EXCLUDED. The steel ring beam, the transfer steels, the 4F hung floor and the flat roof are by others (coordination quantities in the finishes package Bills 6 / 7). Engineer to design: the ring beam + transfers and their bearings on the existing walls (structural survey), the floor-to-wall ties (Class 2B), the hung floor and the roof joists.

CONTENTS

Section	Description	Sheet	Status	
	Cover & Project Information	**Cover**		
	Contents	**Contents**		
	Indicative Programme (Gantt)	**Programme**	*Information*	
	Summary of Tender Pricing	**Summary**		
A	Preliminaries	**A_Preliminaries**	*Contractor priced*	
B	ICF Kit Supply	**B_ICF_Supply**	*Distributor + BuildEase*	
C	Concrete Supply, Pump & Placement	**C_Concrete**	*Contractor priced*	
D	Labour — ICF, Floors & Roofs	**D_Labour**	*Contractor priced*	
F	Reference Data (informative only)	**F_Reference**	—	

PROG · INDICATIVE INSTALL PROGRAMME — RESOURCE-LEVELLED, ONE COLUMN PER WORKI

Group-by-group sequential build with a staggered start between groups. ICF install + snag + pour cycles, intermediate floors and roof structure are completed before moving on. Resourcing and durations below are indicative and must be validated by site management. Render / external finish is NOT included in this programme.

Group	Plots	Forms	Weeks	Start wk	W1 M	W1 T	W1 W	W1 T	W1 F	W1 S	W1 S	W2 M	W2 T	W2 W	W2 T	W2 F	W2 S	W2 S
4F storey (4 flats)	1	295	2	1														

LEGEND

	ICF walls — L1 4F storey, 7 courses on the steel ring beam (erection & snag)
	ICF walls — (one lift only on this job: the 4F storey)
	Concrete pour — sized at 60 m3 per pump-day, ICF crew attends, pump on site (roof-level pour: boom reach / line pump by the contractor)
	Curing — pours held to Fridays where possible so the 2 curing days fall on the weekend; a mid-week pour cures 2 working days
	4F hung floor (BY OTHERS) — 1-day slot after the steel ring beam + transfers (by others), before the ICF
	Flat sedum roof structure (PS10 metal-web joists + deck), after the pour

RESOURCING

• 1 ICF crews of 8 trained installers (each crew = 2 four-man gang-equivalents) erect the wall lifts, moving to the next ready block while a floor is fitted; 1 joinery crew of 3 fits every intermediate floor and roof (floors 1 day per plot and roofs 1 day per plot - one building = one plot: the 4F hung floor (by others) before the ICF, the flat sedum roof structure after the pour). Programme is resource-levelled day by day (white = block waiting for a crew).

• Total ICF site programme: 2 working weeks (ICF erection, floors and roofs). Section A Preliminaries are quantified against this 2-week programme.

• EXTERNAL RENDER / FINISH IS EXCLUDED from this BOQ and this programme. Where a render system is later specified, allow a separate workstream — per BBA guidance, render cannot begin until the concrete core has cured for a minimum of 28 days after the final pour.

• Concrete pump booked on the pour days for each group (see Section C).

• Lead time for BuildEase Pre-Cut Service: 5–6 weeks from order placement; procurement runs in parallel with mobilisation.

• Programme estimates are provided in good faith and must be verified by the project / site management team.

• WALES: the design must satisfy the Building Regulations 2010 as they apply in Wales and the Welsh Government Approved Documents (Approved Documents Wales, incl. Parts L / O 2022 Wales) - building control by Swansea Council (LABC) or a registered building control approver; NOT the English Approved Documents or the Scottish technical handbooks. BUILDING HEIGHT (ADB Diagram D6, to the floor of the top storey): the new 4F FFL is 12,342 above the rear yard (~12.34 m) and ~15.1 m above the LOWEST adjoining ground (front street ASSUMED ~2.8 m below the rear yard - indicative, from the existing elevations; a measured survey must confirm) - the building is IN THE 11-18 m HEIGHT BAND: ALL fire detailing (external-wall materials and the cladding incl. the EPS faces of the ICF, cavity barriers, fire-stopping, compartmentation, the open-air escape stair and every opening onto it) is governed entirely by building control and a fire engineer. Wales: new flats need an automatic fire suppression (sprinkler) system (Building Regulations 2010 reg 37A as applied in Wales / ADB vol 1 Wales) - by others, building control to confirm. 5 storeys with the new 4F on the existing GF-3F masonry: flats = Consequence Class 2B (Approved Document A) - ties / anchorage, the steel ring beam and the transfer steels are engineer-designed (outside the manufacturer tables). The LABC Warranty technical manual caps ICF at 3 storeys unless an independent engineer inspects each pour (pre-pour) and signs off - here the ICF is the top storey of a 5-storey building: the warranty provider must confirm.

• DISTRIBUTOR QUOTATION: the Nudura forms and accessories in Section B are supplied by the distributor (Insubloc) at THEIR OWN rates (blank yellow cells - the same quantities as the Distributor BOM rate card); BuildEase / Tremco CPG price ONLY the pre-cut service and the pre-cut delivery. The alignment system is by the distributor (not included).

• Before day 0 (BY OTHERS, not in this ICF BOQ): the steel ring beam on the existing wall heads + the transfer steels under the internal ICF walls and the 4F front wall (INDICATIVE - structural engineer), then the 4F floor hung from them (programme slot, the joinery crew attends). The ICF base = the top of the ring beam.

• Build sequence: 4F hung floor (1 day per plot) -> L1 ICF 7 courses (3,200) on the ring beam -> pour -> cure -> flat sedum roof structure (1 day per plot) on the ICF walls. ICF pours sized at 60 m3 per pump per day from the lift's own concrete volume.

• PROGRAMME (BOQ Builder sheet 'Programme', 1 ICF crew of 8 + 1 joinery crew of 3; floors 1 day per plot and roofs 1 day per plot - one building = one plot): 6 working days = 2 weeks from the start of the 4F floor slot (the steel ring beam and the transfer steels are in place before day 0, by others). Sequence: 4F hung floor (by others) d0-1; ICF L1 4F storey (7 courses) d1-3.8; pour d4-5; cure over the weekend (Friday pour); flat roof structure d5-6. ICF concrete 49.34 m3 (geometric void of the 295 ordered forms - the Distributor BOM quotes ~46.2 m3 net from the core centre lines less the openings) in 1 pump day. ALIGNMENT (by the distributor, NOT in the BuildEase charges): 69 systems / 4 stillages, needed from the ICF start (day 1) to the strike after the cure (day 6) = ~1 week on site.

• Site access: city-centre site, the new storey is at roof level of an occupied / existing 4-storey building - crane / hoist, offloading, scaffold and road / pavement licences by the contractor for the deliveries (12 pallets on the BuildEase stack sheets: the pre-cut pallets by BuildEase, 1 artic load; the stock forms by the distributor).

SUMMARY OF TENDER PRICING

Section totals are carried forward from each Bill section. The pre-priced column carries ONLY the BuildEase charges (pre-cut service + pre-cut delivery, from the Distributor BOM); the ICF forms, accessories, their delivery and the alignment system are priced by the distributor, and Sections A, C and D by the contractor - every contractor / distributor column fills automatically when rates are entered in the section sheets. This BOQ excludes external render / cladding.

Section	Description	BuildEase pre-priced (£)	Distributor / contractor-priced (£)	Section Total (£)	
A	Preliminaries		£0.00	**£0.00**	
B	ICF Kit Supply (forms / accessories / delivery / alignment: distributor; pre-cut + delivery: BuildEase)	£1,927.85	£0.00	**£1,927.85**	
C	Concrete Supply, Pump & Placement		£0.00	**£0.00**	
D	Labour — ICF, Floors & Roofs		£0.00	**£0.00**	
	NET TOTAL (excluding VAT)	**£1,927.85**	**£0.00**	**£1,927.85**	
	VAT @ 20%			£385.57	
	GRAND TOTAL (inclusive of VAT)			**£2,313.42**	

SIGNATURES

Priced by					
Tendered by					
Approved by					

A · PRELIMINARIES

Items priced per working week against the site programme total of 2 weeks (see Programme sheet). Quantities are pre-populated; the contractor inserts the weekly rate.

Ref	Description	Unit	Qty	Rate (£)	Total (£)
A.1	Site set-up, fencing, signage, induction & welfare establishment	item	1		£0.00
A.2	Welfare facilities — canteen, drying, toilets (hire)	wk	2		£0.00
A.3	Contract management & site supervision	wk	2		£0.00
A.4	Health & Safety, RAMS, CDM consultancy	wk	2		£0.00
A.5	Public liability and contract works insurance	item	1		£0.00
A.6	Scaffolding — independent access for ICF erection	wk	2		£0.00
A.7	Plant hire — telehandler / forklift for offload & ICF moves	wk	2		£0.00
A.8	Plant hire — small tools, generators, power & lighting	wk	2		£0.00
A.9	Hoarding / site enclosure / security	wk	2		£0.00
A.10	Temporary services — water, power, lighting (hire)	wk	2		£0.00
A.11	Site clean, waste management & skip rotation	wk	2		£0.00
A.12	Setting out and surveying — engineer's level checks	wk	2		£0.00
A.13	Site take-down, hand-over & demobilisation	item	1		£0.00
A.14	Pre-completion sound test (Approved Document E)	test			£0.00
A.15	Air-tightness test (Approved Document L)	test			£0.00
A.16	Day works allowance	sum			£0.00
	A — PRELIMINARIES SUBTOTAL				**£0.00**

B · ICF KIT SUPPLY

DISTRIBUTOR QUOTATION. Form and accessory quantities are from the BuildEase take-off (the same lines as the Distributor BOM rate card): the distributor inserts THEIR OWN supply rates in the yellow cells - no BuildEase / Nudura material prices are carried. The BuildEase pre-cut service and the pre-cut delivery are the only pre-priced lines. Alignment system: by the distributor (not included in the BuildEase charges).

Ref	Description	Unit	Qty	Rate (£)	Total (£)
B.1 — Nudura ICF Forms (295 forms, L1 4F storey; supply by the distributor - their rate)					
B.1	NUS-I0096-06 Nudura 6in Standard straight form (bundles of 3: 19; rate card NUS-I0096-06, per each)	nr	55		£0.00
B.1	NUS-I0096-06PC Nudura 6in Standard straight form - PRE-CUT by BuildEase (stock form cut to the optimised list) (bundles of 3: 17; rate card NUS-I0096-06, per each)	nr	51		£0.00
B.1	NUS-IX496-06 Nudura 6in XR35 straight form (bundles of 2: 44; rate card NUS-IX496-06, per each)	nr	87		£0.00
B.1	NUS-IX496-06PC Nudura 6in XR35 straight form - PRE-CUT by BuildEase (stock form cut to the optimised list) (bundles of 2: 44; rate card NUS-IX496-06, per each)	nr	88		£0.00
B.1	NUS-IX490-06 Nudura 6in XR35 90 deg corner form (bundles of 4: 4; rate card NUS-IX490-06, per each)	nr	14		£0.00
B.2 — Nudura Accessories (supply by the distributor - their rate; unit as the rate card)					
B.2	NUS-A0ECF-06 End Caps (6in Standard) (64 nr, bundles of 40: 2; rate card per bundle; From openings on L1)	bundle	2		£0.00
B.2	NUS-A0ECF-06 End Caps (6in XR35) (48 nr, bundles of 40: 2; rate card per bundle; From openings on L1)	bundle	2		£0.00
B.2	NUS-ABLOK-06 Form-Lock (6in Standard) (24 nr, bundles of 10: 3; rate card per bundle; Perimeter: 71.8m ÷ 3.048m)	bundle	3		£0.00
B.2	NUS-ABLOK-06 Form-Lock (6in XR35) (43 nr, bundles of 10: 5; rate card per bundle; Perimeter: 129.6m ÷ 3.048m)	bundle	5		£0.00
B.2	NUS-PLINT-06 Lintel Closures (6in Standard) (20 nr, bundles of 60: 1; From openings on L1)	nr	20		£0.00
B.2	NUS-PLINT-06 Lintel Closures (6in XR35) (12 nr, bundles of 60: 1; From openings on L1)	nr	12		£0.00
B.2	NUS-SF-BOX Spray Foam Cans (15 nr, bundles of 12: 2; rate card per bundle; Perimeter: 756.5m)	bundle	2		£0.00
B.2	NUS-ATSTP-00 T-Form Support Straps (140 nr, bundles of 30: 5; 70 T-junction ends × 2)	nr	140		£0.00
B.2	NUS-A0VJC-00 Vertical Joint Clips (820 nr, bundles of 200: 5; Corners: 14×4, C1: 48×4, Other: 286×2)	nr	820		£0.00
B.3 — Distributor Delivery & Alignment System (by the distributor - not in the BuildEase charges)					
B.3	Delivery of the stock forms, corners and accessories to site (156 stock forms + accessories; crane / offload at roof level by the contractor) - by the distributor	item	1		£0.00
B.4	Alignment system - BY THE DISTRIBUTOR, NOT INCLUDED in the BuildEase charges (69 systems: 2 corner + 67 at 1,600 c/c, 4 stillages; peak L1 C6)	system	69		£0.00
	B — DISTRIBUTOR SUPPLY SUBTOTAL (forms, accessories, delivery, alignment - distributor's rates)				**£0.00**
B.5 — BuildEase Pre-Cut Service (pre-priced, fixed BuildEase charge)					
B.5	Pre-cut service - 3D modelling (4th floor - 2 Castle Gardens: 4 windows, 8 doors, 14 corners)	item	1	£490.88	£490.88
B.5	Pre-cut service - manufacturing (cutting the 139 pre-cut forms to the optimised list, labelling, packing)	item	1	£798.88	£798.88
B.6 — BuildEase Pre-Cut Delivery (pre-priced)					
B.6	Pre-cut delivery - Pre-Cut Delivery - Tankersley to Swansea SA1 (215 road miles, approx.): the pre-cut pallets, 1 artic load	load	1	£638.09	£638.09

	B — BUILDEASE CHARGES SUBTOTAL (pre-cut service + pre-cut delivery, pre-priced)				**£1,927.85**

	B — ICF KIT SUPPLY SUBTOTAL				**£1,927.85**

C · CONCRETE SUPPLY, PUMP & PLACEMENT

Volumes are geometric void calculations (block length × course height × core thickness). Allow ~3% for plastic web displacement and ~5% wastage when ordering. Rates to be inserted by the contractor.

Ref	Description	Unit	Qty	Rate (£)	Total (£)
C.1 — Ready-Mix Concrete Supply (C28/35 typical to BS 8500)					
C.1	Ready-mix concrete — 4F storey (4 flats) (1 plot(s), geometric void)	m³	49.34		£0.00
C.2 — Concrete Pump Hire					
C.2	Boom pump hire — 4F storey (4 flats)	day	1		£0.00
C.2	Pump mobilisation / demobilisation	item	1		£0.00
C.3 — Concrete Vibration & Placement Plant					
C.3	Internal poker vibrator hire — site duration	wk	2		£0.00
C.3	Concrete banksman / poker operator	day			£0.00
	C — CONCRETE SUBTOTAL				**£0.00**

D · LABOUR — ICF INSTALL, FLOORS & ROOFS

ICF install days scaled proportionately against the Maycroft reference (52.65 forms per gang-day). Rates below are per 4-man gang per day. Floor and roof allowances are taken per group from the project configuration.

Ref	Description	Unit	Qty	Rate (£)	Total (£)
D.1 — ICF Install Gang					
D.1	ICF install — 4F storey (4 flats) (295 forms ÷ 52.65 forms/day = 5.6 gang-days)	gang-day	5.60		£0.00
D.1	Snag, pour & cure attendance (30% allowance, project total)	gang-day	1.70		£0.00
D.2 — 4F Hung Floor (PS10 metal-web joists hung from the steel ring beam, BY OTHERS - a 1-day slot before the ICF; joinery crew attends)					
D.2	Floor structure — 4F storey (4 flats) (1 floor × 1 gang-days)	gang-day	1		£0.00
D.3 — Flat Roof Structure Labour (PS10 metal-web joists + deck on the ICF walls, after the pour)					
D.3	Roof structure — 4F storey (4 flats)	gang-day	1		£0.00
	D — LABOUR SUBTOTAL				**£0.00**

F · REFERENCE DATA (informative only)

Per-group quantities calculated from the BuildEase take-off models. Values feed into Sections C and D. Render is excluded from this BOQ.

Group	Plots	Forms	Concrete (m³)	ICF install days	Floor + Roof days	Pre-cut (£)
4F storey (4 flats)	1	295	49.34	5.60	2	£1,289.76
SITE	**1**	**295**	**49.34**	**5.60**	**2**	**£1,289.76**

PER-LIFT FORM BREAKDOWN

Group	Lift	4" Std	6" XR35 str	6" XR35 cnr	10" Std	Lift total
4F storey (4 flats)	L1	0	281	14	0	295

GEOMETRIC CONSTANTS & CALCULATION BASIS

Block length	2.438 m	*96 inches*
Course height	0.4574 m	*18 inches*
4" Std straight volume	0.1133 m³	*Volume = length × course × core*
6" XR35 straight volume	0.1699 m³	*Volume = length × course × core*
10" Std straight volume	0.2832 m³	*Volume = length × course × core*
4" Std corner volume	0.0511 m³	*L-void; long 31.625" / short 15.625"*
6" XR35 corner volume	0.1133 m³	*L-void; long 43" / short 27"*
Maycroft install rate	52.65 forms/day	*Reference: 1053 forms ÷ 20 days*

Bill of Quantities Package - Finishes & Ancillary Trades

ES26-055 | 2 Castle Gardens, Swansea - new 4th-floor storey | Insubloc (Tim Evans) - Nudura distr

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the ICF package (the Nudura formwork and accessories supplied and priced by the distributor, and the BuildEase pre-cut service and delivery) and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer, fire engineer or supplier) before use. Quantities are measured from the BuildEase quotation model of the Huw Griffiths Architects planning drawings HG-24-02-05 / -06 rev 03 (October 2025, 1:100: proposed 4F plan, roof plan, elevations) and the existing drawings HG-24-02-02 / -03; no allowance for waste is included unless stated. Quantity columns are the zones FL (4F floor zone) / L1 (4F storey) / RF (roof); the Site total is their sum. The existing building is excluded. Rates and amounts are by others.

Project	2 Castle Gardens, Swansea - new 4th-floor storey
Site	2 Castle Gardens, Swansea SA1
Client	Insubloc (Tim Evans) - Nudura distributor
Architect	Huw Griffiths Architects Ltd (planning drawings HG-24-02-05 / -06 rev 03, October 2025, 1:100; existing HG-24-02-02 / -03)
Quotation ref	ES26-055
Document	Bill of Quantities Package - Finishes & Ancillary Trades
Date	02/11/2026
Scope	NEW FOURTH-FLOOR STOREY ONLY (4 x 2-bed flats, ~43 m2 each, the open-air stairwell between them and a covered terrace at the front) on a steel ring beam over the existing GF-3F masonry building (EXCLUDED): Nudura 7 courses (3,200) - 6in XR35 external walls incl. the covered-terrace side returns + 6in Standard stair-core and flat-separating walls, 12 openings, 1 stack joint (rear wall, through R02); the ring beam, transfers and the hung 4F floor by others; TLSTF timber partitions; flat sedum / wildflower roof on PS10 joists
Wales / building height	**WALES: the design must satisfy the Building Regulations 2010 as they apply in Wales and the Welsh Government Approved Documents (Approved Documents Wales, incl. Parts L / O 2022 Wales) - building control by Swansea Council (LABC) or a registered building control approver; NOT the English Approved Documents or the Scottish technical handbooks. BUILDING HEIGHT (ADB Diagram D6, to the floor of the top storey): the new 4F FFL is 12,342 above the rear yard (~12.34 m) and ~15.1 m above the LOWEST adjoining ground (front street ASSUMED ~2.8 m below the rear yard - indicative, from the existing elevations; a measured survey must confirm) - the building is IN THE 11-18 m HEIGHT BAND: ALL fire detailing (external-wall materials and the cladding incl. the EPS faces of the ICF, cavity barriers, fire-stopping, compartmentation, the open-air escape stair and every opening onto it) is governed entirely by building control and a fire engineer. Wales: new flats need an automatic fire suppression (sprinkler) system (Building Regulations 2010 reg 37A as applied in Wales / ADB vol 1 Wales) - by others, building control to confirm. 5 storeys with the new 4F on the existing GF-3F masonry: flats = Consequence Class 2B (Approved Document A) - ties / anchorage, the steel ring beam and the transfer steels are engineer-designed (outside the manufacturer tables). The LABC Warranty technical manual caps ICF at 3 storeys unless an independent engineer inspects each pour (pre-pour) and signs off - here the ICF is the top storey of a 5-storey building: the warranty provider must confirm.**
Engineer / specialists	**ENGINEER / SPECIALISTS TO DESIGN: STRUCTURAL ENGINEER: the steel ring beam on the existing wall heads and the transfer steels under the 4F front wall, the two stair-core walls and the flat-separating walls (INDICATIVE in the model), their bearings on the existing walls (structural survey of the existing walls / foundations), the hung 4F floor and the roof joists on the ICF (ledger fixings into the core), the covered-terrace edge beam in pockets in the ICF returns, the floor-to-wall ties (Consequence Class 2B, 5 storeys). FIRE ENGINEER / BUILDING CONTROL (WALES): 11-18 m height band - the external wall finish over the EPS, cavity barriers, the open-air escape stair, the flat entrance doors and the bedroom windows onto it, compartmentation of the new floor over the existing flats, the automatic fire suppression (sprinkler) system required for new flats in Wales. NOT FOR CONSTRUCTION.**
Prepared by	BuildEase (Tremco CPG UK) - BuildEase Design Suite quotation model
Status	**FOR INFORMATION, COORDINATION AND PRICING BY OTHERS - rates blank; NOT part of the ICF package; NOT FOR CONSTRUCTION**

PACKAGE OVERVIEW - pricing by others (all amounts formula-linked to each bill's Package Summary)

Bill	Package	Code / NRM2	Supply £	Install £	Total £
Bill 1	External Wall Finish to the ICF (as the architect's specification), Reveals, Floor-zone Band, Fire Stopping	EXT NRM2 14 / 15	£0.00	£0.00	£0.00
Bill 2	Internal Linings - ICF Walls, Core / Separating Walls, Partitions, Ceilings, Tape, Beads & Skim	DRY NRM2 28	£0.00	£0.00	£0.00
Bill 3	Internal Doors & Ironmongery	JOI NRM2 24	£0.00	£0.00	£0.00
Bill 4	Joinery - Skirtings, Architraves, Window Boards; Common Stair & Balustrades (indicative)	JOI NRM2 22	£0.00	£0.00	£0.00
Bill 5	Timber Stud Partitions (TLSTF) - Framing, Openings, Head Restraint, Pattresses & Fixings	JOI NRM2 16	£0.00	£0.00	£0.00
Bill 6	Structure - Steel Ring Beam & Transfers, 4F Hung Floor, Covered-terrace Floor (coordination); Existing Building Excluded	STR / FLR NRM2 14 / 16 / 18	£0.00	£0.00	£0.00

Bill 7	Flat Sedum Roof - PS10 Joists, Warm-roof Build-up, Upstands, Wall-head Capping, Outlets & Terrace Soffit	RFS / RFC NRM2 16 / 18	£0.00	£0.00	£0.00
Bill 8	Opening Schedule - Lift-and-slide Doors, Flat Entrance Doors, Windows; Terrace & Juliet Balustrades	WIN / MET NRM2 25	£0.00	£0.00	£0.00
	GRAND TOTAL - finishes / ancillary trades, net (excl. VAT)		**£0.00**	**£0.00**	**£0.00**

Optional additions (enter %; blank = 0)		**%**		**Amount £**
Preliminaries	on the finishes net grand total			£0.00
Overheads & profit	on net total + preliminaries			£0.00
Contingency	on net total + preliminaries + OH&P			£0.00
	GRAND TOTAL finishes incl. preliminaries, OH&P and contingency (excl. VAT)			**£0.00**

ICF PACKAGE HOOK - BuildEase BOQ Builder (ICF kit, concrete, labour, preliminaries, programme)	
ICF package (BuildEase BOQ Builder sheets of this workbook: Summary NET TOTAL - the distributor's ICF kit at their rates + the BuildEase pre-cut service and delivery GBP 1,927.85)	**£1,927.85**
COMBINED TOTAL - finishes package (incl. additions) + ICF package, excl. VAT	**£1,927.85**

Pale-yellow cells are the only inputs (rates on each bill sheet, percentages and the ICF hook here). Everything else is a locked formula (protection has no password). Schedules A to D are reference only and are not priced. Named cells: FINISHES_NET_TOTAL, FINISHES_GRAND_TOTAL, ICF_PACKAGE_TOTAL, COMBINED_TOTAL.

IMPORTANT - This information is supplied in good faith for guidance and coordination only. It is not part of the ICF package (the Nudura formwork and accessories supplied and priced by the distributor, and the BuildEase pre-cut service and delivery) and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer, fire engineer or supplier) before use. Quantities are measured from the BuildEase quotation model of the Huw Griffiths Architects planning drawings HG-24-02-05 / -06 rev 03 (October 2025, 1:100: proposed 4F plan, roof plan, elevations) and the existing drawings HG-24-02-02 / -03; no allowance for waste is included unless stated. Quantity columns are the zones FL (4F floor zone) / L1 (4F storey) / RF (roof); the Site total is their sum. The existing building is excluded. Rates and amounts are by others.

KEY QUANTITIES (site totals: new 4F storey, zones FL / L1 / RF, net; linked to the bills)		
External wall finish to the ICF (east, rear, terrace, stairwell)	**205.74**	m2
Neighbour-side faces (provisional)	**76.62**	m2
Wall linings (ICF faces, core / separating walls, partitions, reveals)	**488.76**	m2
Flat ceilings	**164.71**	m2
Skim coat	**653.47**	m2
Internal doorsets	**12.00**	nr
Skirting	**188.45**	m
Timber stud partitions (gross area)	**141.78**	m2
Partition door openings formed	**12.00**	nr
4F hung floor deck (by others)	**203.62**	m2
Steel ring beam + transfers + edge beam (indicative)	**120.53**	m
Flat sedum roof (warm roof)	**193.28**	m2
Wall-head capping	**107.96**	m
Opening schedule units (doors + windows)	**12.00**	nr

Document control

Issue	Description	Date	By / Status
-	Quotation: finishes / ancillary-trades BOQ package for the Nudura ICF distributor quotation (new 4F storey, zones FL / L1 / RF), merged with the BuildEase BOQ Builder ICF bill + programme. Live pricing workbook: rates blank for pricing by others; ICF_PACKAGE_TOTAL linked to the BOQ Builder NET TOTAL	02/11/2026	BuildEase - T. Smith / For information / pricing by others - NOT FOR CONSTRUCTION

Contents

Finishes Cover (this sheet) - overview
General Notes
Summary of Bills (section breakdown)
Finishes Bill 1 External Finish
Finishes Bill 2 Internal Lining
Finishes Bill 3 Doors
Finishes Bill 4 Joinery
Finishes Bill 5 Partitions
Finishes Bill 6 Structure Floor
Finishes Bill 7 Roof
Finishes Bill 8 Openings
Schedule A Areas (not priced)
Schedule B Openings (not priced)
Schedule C Per Flat (not priced)
Schedule D Partitions (not priced)

General Notes, Measurement Basis, Assumptions & Exclusions

ES26-055 | 2 Castle Gardens, Swansea - new 4th-floor storey | Insubloc (Tim Evans) - Nudura distributor

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the ICF package (the Nudura formwork and accessories supplied and priced by the distributor, and the BuildEase pre-cut service and delivery) and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer, fire engineer or supplier) before use. Quantities are measured from the BuildEase quotation model of the Huw Griffiths Architects planning drawings HG-24-02-05 / -06 rev 03 (October 2025, 1:100: proposed 4F plan, roof plan, elevations) and the existing drawings HG-24-02-02 / -03; no allowance for waste is included unless stated. Quantity columns are the zones FL (4F floor zone) / L1 (4F storey) / RF (roof); the Site total is their sum. The existing building is excluded. Rates and amounts are by others.

1 Purpose, status, Wales and building height

WALES: the design must satisfy the Building Regulations 2010 as they apply in Wales and the Welsh Government Approved Documents (Approved Documents Wales, incl. Parts L / O 2022 Wales) - building control by Swansea Council (LABC) or a registered building control approver; NOT the English Approved Documents or the Scottish technical handbooks. BUILDING HEIGHT (ADB Diagram D6, to the floor of the top storey): the new 4F FFL is 12,342 above the rear yard (~12.34 m) and ~15.1 m above the LOWEST adjoining ground (front street ASSUMED ~2.8 m below the rear yard - indicative, from the existing elevations; a measured survey must confirm) - the building is IN THE 11-18 m HEIGHT BAND: ALL fire detailing (external-wall materials and the cladding incl. the EPS faces of the ICF, cavity barriers, fire-stopping, compartmentation, the open-air escape stair and every opening onto it) is governed entirely by building control and a fire engineer. Wales: new flats need an automatic fire suppression (sprinkler) system (Building Regulations 2010 reg 37A as applied in Wales / ADB vol 1 Wales) - by others, building control to confirm. 5 storeys with the new 4F on the existing GF-3F masonry: flats = Consequence Class 2B (Approved Document A) - ties / anchorage, the steel ring beam and the transfer steels are engineer-designed (outside the manufacturer tables). The LABC Warranty technical manual caps ICF at 3 storeys unless an independent engineer inspects each pour (pre-pour) and signs off - here the ICF is the top storey of a 5-storey building: the warranty provider must confirm.

1.1

ENGINEER / SPECIALISTS TO DESIGN (steels, floors, roof joists, partitions and glazing are in the model for coordination only): STRUCTURAL ENGINEER: the steel ring beam on the existing wall heads and the transfer steels under the 4F front wall, the two stair-core walls and the flat-separating walls (INDICATIVE in the model), their bearings on the existing walls (structural survey of the existing walls / foundations), the hung 4F floor and the roof joists on the ICF (ledger fixings into the core), the covered-terrace edge beam in pockets in the ICF returns, the floor-to-wall ties (Consequence Class 2B, 5 storeys).

1.2

This package presents the finishes and ancillary-trade quantities measured by BuildEase alongside the Nudura ICF distributor quotation for 2 Castle Gardens, Swansea - new 4th-floor storey (ref ES26-055). It is set out as a Bill of Quantities so that the client, their quantity surveyor and trade contractors can price and coordinate the works.

1.3

Status: FOR INFORMATION, COORDINATION AND PRICING BY OTHERS - NOT FOR CONSTRUCTION. Supply and install rates are left blank deliberately - BuildEase / Tremco CPG are not pricing these trades. The Excel workbook is a live pricing document: enter rates and every amount, subtotal and total updates by formula.

1.4

The ICF kit (distributor's rates), the BuildEase pre-cut service and delivery, the concrete core, pumping, ICF / floor / roof labour and the build programme are in the BuildEase BOQ Builder sheets of this workbook (Cover / Programme / Summary / A-F). The finishes cover carries a named hook (ICF_PACKAGE_TOTAL) linked to that NET TOTAL.

1.5

PROGRAMME (BOQ Builder sheet 'Programme', 1 ICF crew of 8 + 1 joinery crew of 3; floors 1 day per plot and roofs 1 day per plot - one building = one plot): 6 working days = 2 weeks from the start of the 4F floor slot (the steel ring beam and the transfer steels are in place before day 0, by others). Sequence: 4F hung floor (by others) d0-1; ICF L1 4F storey (7 courses) d1-3.8; pour d4-5; cure over the weekend (Friday pour); flat roof structure d5-6. ICF concrete 49.34 m3 (geometric void of the 295 ordered forms - the Distributor BOM quotes ~46.2 m3 net from the core centre lines less the openings) in 1 pump day. ALIGNMENT (by the distributor, NOT in the BuildEase charges): 69 systems / 4 stillages, needed from the ICF start (day 1) to the strike after the cure (day 6) = ~1 week on site.

1.6

This information is supplied in good faith for guidance and coordination only. It is not part of the ICF package (the Nudura formwork and accessories supplied and priced by the distributor, and the BuildEase pre-cut service and delivery) and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer, fire engineer or supplier) before use.

1.7

Quantities are measured from the BuildEase quotation model of the Huw Griffiths Architects planning drawings HG-24-02-05 / -06 rev 03 (October 2025, 1:100: proposed 4F plan, roof plan, elevations) and the existing drawings HG-24-02-02 / -03; no allowance for waste is included unless stated. Quantity columns are the zones FL (4F floor zone) / L1 (4F storey) / RF (roof); the Site total is their sum. The existing building is excluded. Rates and amounts are by others.

1.8

2 Basis of measurement

Measured generally in accordance with the principles of NRM2 (RICS New Rules of Measurement): work measured net as fixed in position, grouped by work section, units m / m2 / nr / item. NRM2 is referenced for structure only; descriptions are BuildEase's own.

2.1

Quantities are NET. No allowance for waste, laps, cutting or breakage is included unless stated; an "Order guide" with a stated waste % is guidance only.

2.2

Quantity columns: one column PER ZONE - FL the 4F floor zone (ring beam, transfers, hung floor, terrace floor), L1 the new 4F storey, RF the roof. One building: the Site total is the sum of the columns (multiplier 1) and is a live formula.

2.3

Sources: Huw Griffiths Architects planning drawings HG-24-02-05 (proposed plans) / -06 (proposed elevations) rev 03 (October 2025, 1:100) and the existing drawings HG-24-02-02 / -03; the BuildEase quotation model 03_Models/CG_build.skp through its spec (04_Logs/specs/CG_spec.json, CG_partitions_tlstf.json), build reports (04_Logs/build: cgf_floor_4F / cgf_floor_RF / cgf_steel, bcw_fit, BCP_* TLSTF partitions) and the Report Tool component export (04_Logs/takeoff/CG_components.json: inner / outer EPS face areas of the 348 modelled forms, openings net). Measured offline by 05_Scripts/cg_boq.py (no live model).

2.4

3 Assumptions

Walls: external 6in XR35 (355.6 overall) incl. the covered-terrace side returns; the two stair-core walls and the two flat-separating walls 6in Standard (285.75). ICF 7 courses 12,320-15,520.4 on the steel ring beam. Frames tight to the back of the outer EPS: internal reveals XR35 211 / Std 176.

3.1

Levels (model Z above the rear yard, ~+14.92 AOD): existing wall head ~12,066; ring-beam top / ICF base 12,320; 4F FFL 12,342; flat ceiling (roof-joist underside) 14,846; finished sedum ~15,401; ICF top 15,520.4 (119 upstand).

3.2

External finish: NOT specified on the planning elevations - measured as a finish system "as the architect's specification" per elevation / zone; the stairwell is open to atmosphere so its faces are external; the west side wall faces the taller neighbour (finish only where exposed - provisional).

3.3

Floor: the hung 4F floor (PS10 joists + 22 deck) and its insulation / acoustic layers are by others; the covered-terrace floor waterproofed. Roof: warm flat roof 22 deck + VCL + 180 PIR + membrane + 100 sedum; falls not modelled.

3.4

Internal doors: 12 doorsets / 12 leaves from the TLSTF door report; leaves = the largest standard 1,981 leaf that fits the opening less 68. Partitions: TLSTF 38 x 89 C16 - 4F 24 walls 56.6 m x 2,504 (12 wet-room walls), 12 door openings. 1 shower-room privacy set per flat (ASSUMED).

3.5

4 Exclusions (not measured in this package)

The EXISTING BUILDING (GF-3F masonry): structure, the existing roof under the new floor, the existing common stair below 4F, services, the existing cladding / render, party-wall works - all EXCLUDED.

4.1

The Nudura ICF formwork and accessories (supplied and priced by the distributor) and the BuildEase pre-cut service / delivery: in the BOQ Builder Section B. ICF wall concrete, pumping, ICF / floor / roof labour and preliminaries are in the BOQ Builder sheets.

4.2

Floor finishes, decorations, kitchens, sanitaryware, M&E services (heating, MVHR, electrics, sprinklers, door entry) and builder's work.

4.3

4.4 Fire-stopping and fire-rated service penetrations, sealants and mastics, except where expressly described.

5 Open items / to be confirmed

STRUCTURAL ENGINEER: the steel ring beam on the existing wall heads and the transfer steels under the 4F front wall, the two stair-core walls and the flat-separating walls (INDICATIVE in the model), their bearings on the existing walls (structural survey of the existing walls / foundations), the hung 4F floor and the roof joists on the ICF (ledger fixings into the core), the covered-terrace edge beam in pockets in the ICF returns, the floor-to-wall ties (Consequence Class 2B, 5 storeys).

5.1

FIRE ENGINEER / BUILDING CONTROL (WALES): 11-18 m height band - the external wall finish over the EPS, cavity barriers, the open-air escape stair, the flat entrance doors and the bedroom windows onto it, compartmentation of the new floor over the existing flats, the automatic fire suppression (sprinkler) system required for new flats in Wales.

5.2

ARCHITECT: the external wall finish (no material notes on HG-24-02-06), the parapet - the ICF tops are only 119 above the finished sedum (min 150 membrane upstand), the 3,200 ICF height vs ~3,150 drawn, the rear Juliet guarding, the common stair 3F-4F in the stairwell, the neighbour-side (west) wall finish where it shows above the neighbour.

5.3

ACOUSTICIAN: Part E - the new 4F floor is a separating floor over the existing flats, the flat-separating and stair-core ICF walls (not Robust Details: pre-completion sound testing).

5.4

LABC WARRANTY: the ICF is the top storey of a 5-storey building - the 3-storey ICF cap / independent pre-pour inspections: provider to confirm.

5.5

SITE: city-centre site, works at roof level over an existing building - crane / hoist, scaffold, pavement / road licences, the existing occupants and the Party Wall etc. Act 1996 (the neighbour on the west side) by the contractor.

5.6

Assumed (not drawn / not modelled): front street ~2.8 m below the rear yard (height); the 4F flush with the existing rear; the terrace side returns in ICF; core bedroom windows 1,750 x 1,200 head 2,100; 1 privacy set per flat; the 3F floor level for the stair; outlets 1 per bay + 1 overflow; the shower-room tile backer; the floor insulation / resilient layer quantities.

5.7

6 What IS in the ICF package (Distributor BOM ES26-055)

Nudura ICF kit as modelled in the BuildEase Design Suite: 348 forms modelled / 295 to order after the cut optimiser (6in XR35 external walls + 6in Standard stair-core / flat-separating walls) + accessories (end caps, Form-Lock, lintel closures, T-form straps, VJC clips, spray foam) - SUPPLIED AND PRICED BY THE DISTRIBUTOR (rate card; no BuildEase / Nudura material prices in this BOQ).

6.1

BuildEase Pre-Cut Service GBP 1,289.76 (modelling 490.88 + manufacturing 798.88) and the pre-cut delivery GBP 638.09 (Pre-Cut Delivery - Tankersley to Swansea SA1 (215 road miles, approx.), 1 load) = GBP 1,927.85 - the only BuildEase charges.

6.2

6.3 Alignment system (69 systems / 4 stillages): by the distributor, NOT included.

6.4 Nothing in Bills 1 to 8 of this finishes package is included in the ICF package.

7 Pricing instructions to tenderers

Each bill item has a SUPPLY rate and an INSTALL rate. Insert rates only in the pale-yellow cells of the Excel workbook: Supply = Site total qty x Supply rate; Install = Site total qty x Install rate; Line total = Supply + Install. Items measured as "item" are lump sums: the rate entered is the amount.

7.1

Each bill ends with a Package Summary (section subtotals for Supply / Install / Total and the package total). The Cover carries the full overview: one row per bill, grand totals, optional Preliminaries, Overheads & profit and Contingency percentages (pale-yellow cells; blank = 0) and the ICF package hook.

7.2

All other cells are locked by sheet protection (no password - Review > Unprotect Sheet if a change is genuinely needed) so formulas cannot be overwritten by accident.

7.3

Re-measure and verify all quantities before pricing or ordering. State any qualification against the item in the Notes column.

7.4

The Order guide figures and Schedules A to D are not measured bill items and must not be priced as such. All amounts exclude VAT.

7.5

Summary of Bills - section breakdown

ES26-055 | 2 Castle Gardens, Swansea - new 4th-floor storey | Insubloc (Tim Evans) - Nudura distributor - amounts by others, excl. VAT

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the ICF package (the Nudura formwork and accessories supplied and priced by the distributor, and the BuildEase pre-cut service and delivery) and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer, fire engineer or supplier) before use. Quantities are measured from the BuildEase quotation model of the Huw Griffiths Architects planning drawings HG-24-02-05 / -06 rev 03 (October 2025, 1:100: proposed 4F plan, roof plan, elevations) and the existing drawings HG-24-02-02 / -03; no allowance for waste is included unless stated. Quantity columns are the zones FL (4F floor zone) / L1 (4F storey) / RF (roof); the Site total is their sum. The existing building is excluded. Rates and amounts are by others.

Bill	Section	Description	Supply £	Install £	Total £
1	1A	External wall finish to the ICF - AS THE ARCHITECT'S SPECIFICATION (NRM2 14 / 15 - package EXT; system by others, SPEC TBC)	£0.00	£0.00	£0.00
1	1B	Coordination items (supply by others)	£0.00	£0.00	£0.00
Bill 1 - External Wall Finish to the ICF (as the architect's specification), Reveals, Flo			**£0.00**	**£0.00**	**£0.00**
2	2A	Wall linings (NRM2 28 / package DRY)	£0.00	£0.00	£0.00
2	2B	Ceilings (NRM2 28 / package DRY)	£0.00	£0.00	£0.00
2	2C	Jointing, beads and skim (NRM2 28 / package DRY)	£0.00	£0.00	£0.00
Bill 2 - Internal Linings - ICF Walls, Core / Separating Walls, Partitions, Ceilings, Ta			**£0.00**	**£0.00**	**£0.00**
3	3A	Internal doorsets (NRM2 24 / package JOI)	£0.00	£0.00	£0.00
3	3B	Ironmongery (NRM2 24 / package JOI)	£0.00	£0.00	£0.00
Bill 3 - Internal Doors & Ironmongery (package JOI)			**£0.00**	**£0.00**	**£0.00**
4	4A	Skirtings (NRM2 22 / package JOI)	£0.00	£0.00	£0.00
4	4B	Architraves (NRM2 22 / package JOI)	£0.00	£0.00	£0.00
4	4C	Window boards (NRM2 22 / package JOI)	£0.00	£0.00	£0.00
4	4D	Common stair, landings, balustrades and sundry joinery - INDICATIVE, not modelled (NRM2 22 / package JOI / MET)	£0.00	£0.00	£0.00
Bill 4 - Joinery - Skirtings, Architraves, Window Boards; Common Stair & Balustrades (			**£0.00**	**£0.00**	**£0.00**
5	5A	Timber stud partitions, non-loadbearing - framing (NRM2 16 / package JOI)	£0.00	£0.00	£0.00
5	5B	Partition timber - supply (NRM2 16 / package JOI)	£0.00	£0.00	£0.00
5	5C	Forming door openings in partitions (NRM2 16 / package JOI)	£0.00	£0.00	£0.00
5	5D	Head restraint, pattresses, acoustic and fixings (NRM2 16 / package JOI)	£0.00	£0.00	£0.00
Bill 5 - Timber Stud Partitions (TLSTF) - Framing, Openings, Head Restraint, Pattresse			**£0.00**	**£0.00**	**£0.00**
6	6A	Steel ring beam, transfer steels and terrace edge beam (NRM2 14 - package STR; STRUCTURAL ENGINEER - INDICATIVE, by others)	£0.00	£0.00	£0.00
6	6B	4F hung floor - PS10 metal-web joists hung from the steels (NRM2 16 - package FLR; floor designer / engineer, by others)	£0.00	£0.00	£0.00
6	6C	Covered terrace floor (NRM2 18 - package FLR / RFC; by others)	£0.00	£0.00	£0.00
6	6D	Existing building - EXCLUDED (not measured)	£0.00	£0.00	£0.00
Bill 6 - Structure - Steel Ring Beam & Transfers, 4F Hung Floor, Covered-terrace Floor			**£0.00**	**£0.00**	**£0.00**
7	7A	Roof structure - PS10 metal-web joists on the ICF walls (NRM2 16 - package RFS; roof designer / engineer)	£0.00	£0.00	£0.00
7	7B	Roof coverings - warm flat roof with sedum / wildflower (NRM2 18 - package RFC; roofing / green-roof specialist)	£0.00	£0.00	£0.00
7	7C	Covered-terrace soffit (NRM2 18 / 28 - package RFC / EXT)	£0.00	£0.00	£0.00
Bill 7 - Flat Sedum Roof - PS10 Joists, Warm-roof Build-up, Upstands, Wall-head Cappi			**£0.00**	**£0.00**	**£0.00**
8	8A	Opening schedule - one line per unit incl. accessories (NRM2 25 - package WIN; window / door supplier)	£0.00	£0.00	£0.00
8	8B	Balustrades and guarding (NRM2 25 / 22 - package MET)	£0.00	£0.00	£0.00
8	8C	Items not modelled (PROVISIONAL)	£0.00	£0.00	£0.00
Bill 8 - Opening Schedule - Lift-and-slide Doors, Flat Entrance Doors, Windows; Terra			**£0.00**	**£0.00**	**£0.00**
TOTAL - finishes / ancillary trades, net (agrees with the Cover overview)			**£0.00**	**£0.00**	**£0.00**

Schedules A to D are reference schedules and are not priced. Preliminaries, overheads & profit, contingency and the ICF package (BuildEase BOQ Builder) are applied on the Cover.

Bill 1 - External Wall Finish to the ICF (as the architect's specification), Reveals, Floor-zone Band, Fire Stopping

External wall finish to the ICF EPS faces by elevation (east, rear, the covered terrace, the open-air stairwell, the neighbour side), reveals, the floor-zone band over the ring beam and the fire stopping (system by others, spec TBC). [NRM2 14 / 15 / package EXT]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the ICF package (the Nudura formwork and accessories supplied and priced by the distributor, and the BuildEase pre-cut service and delivery) and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer, fire engineer or supplier) before use. Quantities are measured from the BuildEase quotation model of the Huw Griffiths Architects planning drawings HG-24-02-05 / -06 rev 03 (October 2025, 1:100: proposed 4F plan, roof plan, elevations) and the existing drawings HG-24-02-02 / -03; no allowance for waste is included unless stated. Quantity columns are the zones FL (4F floor zone) / L1 (4F storey) / RF (roof); the Site total is their sum. The existing building is excluded. Rates and amounts are by others.

Ref	Description	Unit	FL 4F floor zone	L1 4F storey	RF Roof	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per zone FL / L1 / RF (Site total = sum of the zones)		**1**	**1**	**1**	**3**						Levels: FL = 4F floor zone: steel ring beam on the existing wall heads (~12,066) + transfers, the hung 4F floor (FFL 12,342) and the covered-terrace floor; L1 = the new 4F storey: Nudura 7 courses 12,320-15,520 (4 flats, the open-air stairwell, the covered terrace); RF = flat sedum roof on PS10 joists (finish ~15,401) + the covered-terrace roof
1A	**External wall finish to the ICF - AS THE ARCHITECT'S SPECIFICATION (NRM2 14 / 15 - package EXT; system by others, SPEC TBC)**											
	The planning elevations HG-24-02-06 rev 03 carry NO material notes: the rear elevation shows the new 4F cladding continuous with the existing 3F cladding below. The finish is therefore measured as "external wall finish system to the ICF EPS face AS THE ARCHITECT'S SPECIFICATION" (render on carrier / rainscreen cladding - TBC) by elevation and zone. Areas are the modelled ICF outer EPS faces (Report Tool component export, openings net, full storey height 3,200), plus the terrace-return inner faces and the open-air stairwell faces (the stairwell is open to atmosphere). 11-18 m HEIGHT BAND: the system, its reaction-to-fire class over the EPS, cavity barriers and fire-stopping are governed by building control and a fire engineer (Approved Document B Wales).											
1A.1	East side elevation (the long side over the existing east wall), ICF outer face, full height	m2		76.80		**76.80**			£0.00	£0.00	**£0.00**	Order guide +10% = 84.5; Wall W03 outer faces
1A.2	Rear elevation incl. the two rear corners, net of the two rear lift-and-slide doors (continuous with the existing 3F cladding)	m2		26.44		**26.44**			£0.00	£0.00	**£0.00**	Order guide +10% = 29.1; W02 + CR01 / CR02 outer faces
1A.3	Covered terrace: the flats' front wall outer face, net of the two terrace doors	m2		18.48		**18.48**			£0.00	£0.00	**£0.00**	Order guide +10% = 20.3; W08 outer faces
1A.4	Covered terrace: the inner faces of the two side-wall returns (X 0-2,407) + the two return ends at the terrace front	m2		17.53		**17.53**			£0.00	£0.00	**£0.00**	Order guide +10% = 19.3; Return inner faces (component share) + ends 2 x 356 x 3,200
1A.5	Open-air stairwell: the stairwell faces of the two core walls, net of the 4 flat entrance doors + 4 bedroom windows (escape route - fire engineer)	m2		46.96		**46.96**			£0.00	£0.00	**£0.00**	Order guide +10% = 51.7; Half of W04 / W05 faces
1A.6	Open-air stairwell: the side-wall inner faces between the core walls (both sides)	m2		19.53		**19.53**			£0.00	£0.00	**£0.00**	Order guide +10% = 21.5; Side-wall inner face share in the stairwell
1A.7	West side elevation against the TALLER NEIGHBOUR (drawn as a single line on the plan): weathering / finish ONLY where exposed above the neighbour's roof - PROVISIONAL (party wall surveyor / architect)	m2		76.62		**76.62**			£0.00	£0.00	**£0.00**	W01 outer faces in full - exposed area TBC on a survey
1A.8	External reveal returns at the doors / windows (head + jambs; frames tight to the back of the outer EPS: XR35 102, Std 67 on the stairwell side), incl. stop / reveal beads	m2		5.59		**5.59**			£0.00	£0.00	**£0.00**	Order guide +10% = 6.1
1A.9	Corner / arris beads or corner trims: 2 rear external corners + the 4 arrises of the terrace-return ends, full height	m		19.20		**19.20**			£0.00	£0.00	**£0.00**	Order guide +10% = 21.1
1A.10	Floor-zone band: finish over the steel ring beam / hung-floor zone between the existing wall head (~12,066) and the ICF base (12,320), 254 high, east side + rear (incl. the steel face, insulation and carrier - spec TBC)	m2	8.98			**8.98**			£0.00	£0.00	**£0.00**	(24.858 + 10.509) m x 0.254 - PROVISIONAL
1A.11	Base / starter track, drip and DPC at the junction with the existing 3F cladding / render below (east side + rear), incl. insect mesh	m	35.37			**35.37**			£0.00	£0.00	**£0.00**	Order guide +10% = 38.9
1A.12	Sealant joint between the finish / reveal returns and the window and door frames (backer rod + low-modulus sealant)	m		74.60		**74.60**			£0.00	£0.00	**£0.00**	Order guide +10% = 82.1
1A.13	Movement joints in the finish system (per the system manufacturer, incl. at the floor-zone band / ring beam line)	item							£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount. Allowance - system manufacturer

Ref	Description	Unit	FL 4F floor zone	L1 4F storey	RF Roof	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per zone FL / L1 / RF (Site total = sum of the zones)		**1**	**1**	**1**	**3**						Levels: FL = 4F floor zone: steel ring beam on the existing wall heads (~12,066) + transfers, the hung 4F floor (FFL 12,342) and the covered-terrace floor; L1 = the new 4F storey: Nudura 7 courses 12,320-15,520 (4 flats, the open-air stairwell, the covered terrace); RF = flat sedum roof on PS10 joists (finish ~15,401) + the covered-terrace roof
1A.14	Cavity barriers / fire-stopping in the external wall finish (at the compartment floor line, round openings, at the party / neighbour wall and the stairwell) - 11-18 m band	item							£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount. Fire engineer / building control
1B Coordination items (supply by others)												
1B.1	Door thresholds / weathering at the terrace, rear (Juliet) and stairwell flat-entrance doors (low thresholds, Part M) - by the door supplier	nr		8.00		**8.00**			£0.00	£0.00	**£0.00**	Coordination only
1B.2	External cills to the bedroom windows onto the stairwell (PPC aluminium, bcw_fit cill depth) - with the windows (Bill 8)	nr		4.00		**4.00**			£0.00	£0.00	**£0.00**	Coordination only
1B.3	Rainwater pipes and brackets on the new walls / down the existing building, fixings into the ICF webs (positions per the drainage design)	item							£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount. Bill 7B outlets

PACKAGE SUMMARY - Bill 1 External Wall Finish to the ICF (as the architect's specification), Reveals, Floor-zone Band, Fire Stopping (package EXT; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
1A	External wall finish to the ICF - AS THE ARCHITECT'S SPECIFICATION (NRM2 14 / 15 - package EXT; system by others, SPEC TBC)	£0.00	£0.00	**£0.00**
1B	Coordination items (supply by others)	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 1, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the ICF package (distributor kit / BuildEase charges).

Bill 2 - Internal Linings - ICF Walls, Core / Separating Walls, Partitions, Ceilings, Tape, Beads & Skim

Dry linings to the ICF inner faces of the 4 flats (thermal barrier to the EPS), the core and separating walls (Part E), the TLSTF partitions, reveals and the flat ceilings under the roof joists. [NRM2 28 / package DRY]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the ICF package (the Nudura formwork and accessories supplied and priced by the distributor, and the BuildEase pre-cut service and delivery) and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer, fire engineer or supplier) before use. Quantities are measured from the BuildEase quotation model of the Huw Griffiths Architects planning drawings HG-24-02-05 / -06 rev 03 (October 2025, 1:100: proposed 4F plan, roof plan, elevations) and the existing drawings HG-24-02-02 / -03; no allowance for waste is included unless stated. Quantity columns are the zones FL (4F floor zone) / L1 (4F storey) / RF (roof); the Site total is their sum. The existing building is excluded. Rates and amounts are by others.

Ref	Description	Unit	FL 4F floor zone	L1 4F storey	RF Roof	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per zone FL / L1 / RF (Site total = sum of the zones)		1	1	1	3						Levels: FL = 4F floor zone: steel ring beam on the existing wall heads (~12,066) + transfers, the hung 4F floor (FFL 12,342) and the covered-terrace floor; L1 = the new 4F storey: Nudura 7 courses 12,320-15,520 (4 flats, the open-air stairwell, the covered terrace); RF = flat sedum roof on PS10 joists (finish ~15,401) + the covered-terrace roof
2A	**Wall linings (NRM2 28 / package DRY)**											
	Measured on the modelled ICF EPS faces (component export, openings net) in the lining zone: 4F FFL 12,342 (22 deck on the hung joists) to the underside of the roof joists 14,846 (2,504). Envelope inner faces inside the 4 flats (the side-wall parts in the terrace / stairwell zones are external - Bill 1), the flat-side faces of the two core walls, the separating walls both faces, TLSTF partitions both faces less the door gaps (2,100 high). EPS faces must be covered by a thermal barrier (min. 12.5 mm board, mechanically fixed to the ICF webs) whatever the finish.											
2A.1	ICF external-wall inner faces in the flats (side walls, rear wall, flats' front wall): 12.5 mm wallboard on dabs + mechanical fixings to the ICF webs (MR board in the shower rooms / kitchens)	m2		111.95		**111.95**			£0.00	£0.00	**£0.00**	Order guide +10% = 123.1
2A.2	Stair-core walls (6in Standard) - the flat-side faces: lining to the acoustic / fire design (flat to the common stair)	m2		33.44		**33.44**			£0.00	£0.00	**£0.00**	Order guide +10% = 36.8
2A.3	Flat-separating walls (6in Standard) - both faces: lining to the acoustic design (Part E - ICF is not a Robust Detail: independent lining / dense board as the acoustician; pre-completion sound testing)	m2		90.11		**90.11**			£0.00	£0.00	**£0.00**	Order guide +10% = 99.1
2A.4	TLSTF partitions - both faces: 12.5 mm board on 38 x 89 studs (MR / tile backer in the shower rooms; acoustic board where Part E E2 requires)	m2		240.26		**240.26**			£0.00	£0.00	**£0.00**	Order guide +10% = 264.3
2A.5	Internal reveals to the windows / doors in the ICF, jambs and heads (XR35 211 deep, Std 176 deep): board / bonding + skim	m2		12.99		**12.99**			£0.00	£0.00	**£0.00**	Order guide +10% = 14.3
2A.6	Extra over for tile-backer / cement board in place of plasterboard in the 4 shower rooms, full height	m2		82.03		**82.03**			£0.00	£0.00	**£0.00**	Shower-room boxes (BCP_pattress wet_rooms) perimeter 35.86 m x 2,504 less 1 door each - PROVISIONAL
2B	**Ceilings (NRM2 28 / package DRY)**											
	Flat ceilings fixed to the bottom chords of the PS10 roof joists (14,846) = the 4 flat floor areas between the ICF faces (171.16 m2) less the partition footprints (6.46 m2). Top-storey ceilings under a timber flat roof - board type / fire resistance per the fire strategy. The open-air stairwell has no ceiling; the covered-terrace soffit is in Bill 7C.											
2B.1	Flat ceilings: plasterboard (fire-rated as the fire strategy) on resilient bars / direct to the PS10 bottom chords, incl. noggins at the board edges	m2		164.71		**164.71**			£0.00	£0.00	**£0.00**	Order guide +10% = 181.2
2C	**Jointing, beads and skim (NRM2 28 / package DRY)**											
2C.1	Scrim tape, board joints (walls / 1.2 m; ceilings / 1.2 + 2.4 m)	m		613.18		**613.18**			£0.00	£0.00	**£0.00**	Order guide +10% = 674.5
2C.2	Scrim tape, internal angles wall to wall (4 per flat + 4 per partition)	m		280.45		**280.45**			£0.00	£0.00	**£0.00**	Estimate - no room model; Order guide +10% = 308.5
2C.3	Scrim tape, wall to ceiling angles (flat perimeters + partition heads both sides)	m		223.27		**223.27**			£0.00	£0.00	**£0.00**	Estimate; Order guide +10% = 245.6
2C.4	Angle bead, window / door reveals	m		67.60		**67.60**			£0.00	£0.00	**£0.00**	Order guide +10% = 74.4
2C.5	Skim coat, 2-3 mm, to all net wall, reveal and ceiling board faces	m2		653.47		**653.47**			£0.00	£0.00	**£0.00**	Face layer only
2D	**Ordering guide (not a measured item)**											
2D.1	*Plasterboard to purchase, all types, before waste*	*m2*		*653.47*		*653.47*					*not priced*	*Guide only (+10% waste)*

PACKAGE SUMMARY - Bill 2 Internal Linings - ICF Walls, Core / Separating Walls, Partitions, Ceilings, Tape, Beads & Skim (package DRY; amounts by others, excl. VAT)

Ref	Description	Unit	FL 4F floor zone	L1 4F storey	RF Roof	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per zone FL / L1 / RF (Site total = sum of the zones)		**1**	**1**	**1**	**3**						Levels: FL = 4F floor zone: steel ring beam on the existing wall heads (~12,066) + transfers, the hung 4F floor (FFL 12,342) and the covered-terrace floor; L1 = the new 4F storey: Nudura 7 courses 12,320-15,520 (4 flats, the open-air stairwell, the covered terrace); RF = flat sedum roof on PS10 joists (finish ~15,401) + the covered-terrace roof

Section	Description	Supply £	Install £	Total £
2A	Wall linings (NRM2 28 / package DRY)	£0.00	£0.00	**£0.00**
2B	Ceilings (NRM2 28 / package DRY)	£0.00	£0.00	**£0.00**
2C	Jointing, beads and skim (NRM2 28 / package DRY)	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 2, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the ICF package (distributor kit / BuildEase charges).

Bill 3 - Internal Doors & Ironmongery

Internal doorsets and ironmongery from the TLSTF partition doors (12 doorsets, 12 leaves). [NRM2 24 / package JOI]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the ICF package (the Nudura formwork and accessories supplied and priced by the distributor, and the BuildEase pre-cut service and delivery) and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer, fire engineer or supplier) before use. Quantities are measured from the BuildEase quotation model of the Huw Griffiths Architects planning drawings HG-24-02-05 / -06 rev 03 (October 2025, 1:100: proposed 4F plan, roof plan, elevations) and the existing drawings HG-24-02-02 / -03; no allowance for waste is included unless stated. Quantity columns are the zones FL (4F floor zone) / L1 (4F storey) / RF (roof); the Site total is their sum. The existing building is excluded. Rates and amounts are by others.

Ref	Description	Unit	FL 4F floor zone	L1 4F storey	RF Roof	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per zone FL / L1 / RF (Site total = sum of the zones)		**1**	**1**	**1**	**3**						Levels: FL = 4F floor zone: steel ring beam on the existing wall heads (~12,066) + transfers, the hung 4F floor (FFL 12,342) and the covered-terrace floor; L1 = the new 4F storey: Nudura 7 courses 12,320-15,520 (4 flats, the open-air stairwell, the covered terrace); RF = flat sedum roof on PS10 joists (finish ~15,401) + the covered-terrace roof
3A	**Internal doorsets (NRM2 24 / package JOI)**											
	From the TLSTF door report (12 openings in the partitions, 3 per flat). Leaf = the largest standard 1,981 leaf that fits the opening less 68 (2 x 32 lining + clearances). The 4 flat ENTRANCE doors are in the ICF stair-core walls onto the OPEN-AIR stairwell - external-grade composite doorsets in the opening schedule (Bill 8); their fire rating / self-closing (ADB vol 1 Wales) is for the fire engineer.											
3A.1	Internal doorset, 838 x 1,981 leaf, 32 x 115 lining set (114 partition), stops	nr		8.00		**8.00**			£0.00	£0.00	**£0.00**	A2-P02-D1 (926), A2-P05-D3 (926), A1-P02-D1 (926), A1-P05-D3 (926), B2-P02-D1 (926), B2-P05-D3 (926), B1-P02-D1 (926), B1-P05-D3 (926)
3A.2	Internal doorset, 610 x 1,981 leaf, 32 x 115 lining set (114 partition), stops	nr		4.00		**4.00**			£0.00	£0.00	**£0.00**	A2-P03-D2 (726), A1-P03-D2 (726), B2-P03-D2 (726), B1-P03-D2 (726)
3B	**Ironmongery (NRM2 24 / package JOI)**											
3B.1	Butt hinges, 100 mm, pairs (1.5 pair per leaf)	pr		18.00		**18.00**			£0.00	£0.00	**£0.00**	1.5 pr per leaf
3B.2	Standard sets: tubular latch, lever pair on roses	set		8.00		**8.00**			£0.00	£0.00	**£0.00**	All partition doorsets less the privacy sets
3B.3	Shower-room sets: privacy lock, thumb-turn with emergency release, lever pair	set		4.00		**4.00**			£0.00	£0.00	**£0.00**	ASSUMED 1 per flat (4 shower rooms) - confirm against the door schedule
3B.4	Door stops, floor or skirting mounted	nr		12.00		**12.00**			£0.00	£0.00	**£0.00**	One per leaf
	Flat entrance doors, the terrace and rear lift-and-slide doors and their ironmongery are in Bill 8 (opening schedule).											

PACKAGE SUMMARY - Bill 3 Internal Doors & Ironmongery (package JOI; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
3A	Internal doorsets (NRM2 24 / package JOI)	£0.00	£0.00	**£0.00**
3B	Ironmongery (NRM2 24 / package JOI)	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 3, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the ICF package (distributor kit / BuildEase charges).

Bill 4 - Joinery - Skirtings, Architraves, Window Boards; Common Stair & Balustrades (indicative)

Second-fix joinery measured from the flat outlines, the TLSTF partitions and the spec openings; the common stair in the open-air stairwell indicative. [NRM2 22 / package JOI]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the ICF package (the Nudura formwork and accessories supplied and priced by the distributor, and the BuildEase pre-cut service and delivery) and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer, fire engineer or supplier) before use. Quantities are measured from the BuildEase quotation model of the Huw Griffiths Architects planning drawings HG-24-02-05 / -06 rev 03 (October 2025, 1:100: proposed 4F plan, roof plan, elevations) and the existing drawings HG-24-02-02 / -03; no allowance for waste is included unless stated. Quantity columns are the zones FL (4F floor zone) / L1 (4F storey) / RF (roof); the Site total is their sum. The existing building is excluded. Rates and amounts are by others.

Ref	Description	Unit	FL 4F floor zone	L1 4F storey	RF Roof	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per zone FL / L1 / RF (Site total = sum of the zones)		1	1	1	3						Levels: FL = 4F floor zone: steel ring beam on the existing wall heads (~12,066) + transfers, the hung 4F floor (FFL 12,342) and the covered-terrace floor; L1 = the new 4F storey: Nudura 7 courses 12,320-15,520 (4 flats, the open-air stairwell, the covered terrace); RF = flat sedum roof on PS10 joists (finish ~15,401) + the covered-terrace roof
4A Skirtings (NRM2 22 / package JOI)												
	No room model: every lined wall face at floor level - the 4 flat perimeters between the ICF faces less the terrace / rear / entrance door openings, plus the TLSTF partitions both faces less their door openings.											
4A.1	Skirting 18 x 119 MDF, primed, fixed to the linings (profile by the client)	m		188.45		**188.45**			£0.00	£0.00	**£0.00**	Order guide +10% = 207.3
4B Architraves (NRM2 22 / package JOI)												
	Per face = 2 legs x 2150 + (opening + 2 x 70). Internal doors both faces; the flat entrance doors and the lift-and-slide doors the inside face only (legs to the opening height); windows have plastered reveals (no architrave).											
4B.1	Architrave to the internal doors, both faces, 18 x 69	m		127.18		**127.18**			£0.00	£0.00	**£0.00**	Order guide +10% = 139.9
4B.2	Architrave to the flat entrance and lift-and-slide doors, inside face	m		52.12		**52.12**			£0.00	£0.00	**£0.00**	Order guide +10% = 57.3
4C Window boards (NRM2 22 / package JOI)												
	The 4 bedroom windows onto the stairwell (sills 900 above the ICF base per the spec): board = opening + 2 x 50, depth 176 + 25.											
4C.1	Window board MDF / timber 201 x 1,850 long (openings ~1,750 wide)	nr		4.00		**4.00**			£0.00	£0.00	**£0.00**	L1-CAW1, L1-CAW2, L1-CBW1, L1-CBW2
4D Common stair, landings, balustrades and sundry joinery - INDICATIVE, not modelled (NRM2 22 / package JOI / MET)												
	The stairwell between the core walls (31.1 m2 plan, OPEN TO ATMOSPHERE) carries the common stair up from the existing 3F (3F floor ASSUMED ~9,480 above the rear yard) to the new 4F landings at the flat entrance doors: rise ~2,862 -> 16 risers of 178.9 (common stair max rise 190). Not modelled - geometry by the architect / stair manufacturer; an external escape stair - materials / fire performance by the fire engineer.											
4D.1	Common stair flight(s) 3F to 4F in the open-air stairwell (16 risers) incl. strings, treads, nosings, landings to the 4 flat entrance doors - external grade (galvanised steel / precast - spec TBC)	item		1.00		**1.00**			£0.00	£0.00	**£0.00**	PROVISIONAL - not modelled
4D.2	Handrails + balustrade / guarding 1,100 to the stair and the 4F landings in the stairwell	item		1.00		**1.00**			£0.00	£0.00	**£0.00**	PROVISIONAL
4D.3	Boxings to soil stacks / services (4 flats) and pipe runs	item							£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount. Allowance - positions to the M&E design

PACKAGE SUMMARY - Bill 4 Joinery - Skirtings, Architraves, Window Boards; Common Stair & Balustrades (indicative) (package JOI; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
4A	Skirtings (NRM2 22 / package JOI)	£0.00	£0.00	**£0.00**
4B	Architraves (NRM2 22 / package JOI)	£0.00	£0.00	**£0.00**
4C	Window boards (NRM2 22 / package JOI)	£0.00	£0.00	**£0.00**
4D	Common stair, landings, balustrades and sundry joinery - INDICATIVE, not modelled (NRM2 22 / package JOI / MET)	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 4, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the ICF package (distributor kit / BuildEase charges).

Bill 5 - Timber Stud Partitions (TLSTF) - Framing, Openings, Head Restraint, Pattresses & Fixings

Non-loadbearing 38 x 89 C16 timber stud partitions from the TLSTF model (4F 24 walls 56.6 m x 2,504 (12 wet-room walls), 12 door openings). Linings in Bill 2, doorsets in Bill 3. [NRM2 16 / package JOI]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the ICF package (the Nudura formwork and accessories supplied and priced by the distributor, and the BuildEase pre-cut service and delivery) and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer, fire engineer or supplier) before use. Quantities are measured from the BuildEase quotation model of the Huw Griffiths Architects planning drawings HG-24-02-05 / -06 rev 03 (October 2025, 1:100: proposed 4F plan, roof plan, elevations) and the existing drawings HG-24-02-02 / -03; no allowance for waste is included unless stated. Quantity columns are the zones FL (4F floor zone) / L1 (4F storey) / RF (roof); the Site total is their sum. The existing building is excluded. Rates and amounts are by others.

Ref	Description	Unit	FL 4F floor zone	L1 4F storey	RF Roof	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per zone FL / L1 / RF (Site total = sum of the zones)		1	1	1	3						Levels: FL = 4F floor zone: steel ring beam on the existing wall heads (~12,066) + transfers, the hung 4F floor (FFL 12,342) and the covered-terrace floor; L1 = the new 4F storey: Nudura 7 courses 12,320-15,520 (4 flats, the open-air stairwell, the covered terrace); RF = flat sedum roof on PS10 joists (finish ~15,401) + the covered-terrace roof
5A	**Timber stud partitions, non-loadbearing - framing (NRM2 16 / package JOI)**											
	C16 softwood stud partitions as built in the TLSTF model (4F 24 walls 56.6 m x 2,504 (12 wet-room walls), 12 door openings): 38 x 89 studs at 600 c/c (400 in the wet-room walls: bc_int_89_400 12, bc_int_89_600 12), head and bottom rails, noggins. FFL 12,342 to 5 mm under the roof-joist bottom chord (2,504). Gross area, door openings NOT deducted (5C). The core and separating walls are ICF (Nudura).											
5A.1	Flat A1 partitions (6 walls, 14.16 m x 2,504): 38 x 89 C16 studs, head + bottom rails, noggins	m2		35.45		**35.45**			£0.00	£0.00	**£0.00**	wall length x height
5A.2	Flat A2 partitions (6 walls, 14.16 m x 2,504): 38 x 89 C16 studs, head + bottom rails, noggins	m2		35.45		**35.45**			£0.00	£0.00	**£0.00**	wall length x height
5A.3	Flat B1 partitions (6 walls, 14.16 m x 2,504): 38 x 89 C16 studs, head + bottom rails, noggins	m2		35.45		**35.45**			£0.00	£0.00	**£0.00**	wall length x height
5A.4	Flat B2 partitions (6 walls, 14.16 m x 2,504): 38 x 89 C16 studs, head + bottom rails, noggins	m2		35.45		**35.45**			£0.00	£0.00	**£0.00**	wall length x height
5B	**Partition timber - supply (NRM2 16 / package JOI)**											
	ESTIMATE in linear metres of 38 x 89 C16 kiln-dried sawn softwood: studs from the TLSTF verify report (162 studs x stud length 2,466.0), bottom rails (door gaps cut out) + head rails, one noggin row and 2 king studs + head per door. TLSTF members: 760. Reconcile against the TLSTF construction extract before ordering. Supply only.											
5B.1	38 x 89 C16 kiln-dried sawn softwood: studs (TLSTF stud counts x stud length)	m		399.49		**399.49**			£0.00	£0.00	**£0.00**	Estimate - see 5B note
5B.2	38 x 89 C16 kiln-dried sawn softwood: bottom + head rails	m		102.93		**102.93**			£0.00	£0.00	**£0.00**	Estimate - see 5B note
5B.3	38 x 89 C16 kiln-dried sawn softwood: noggins (one row)	m		46.31		**46.31**			£0.00	£0.00	**£0.00**	Estimate - see 5B note
5B.4	38 x 89 C16 kiln-dried sawn softwood: king studs and heads at door openings	m		70.41		**70.41**			£0.00	£0.00	**£0.00**	Estimate - see 5B note
5B.5	*38 x 89 C16 lengths to order (run +10%, 4.8 m lengths)*	*nr*		*142.00*		*142.00*					*not priced*	*Ordering guide only - not priced in addition*
5C	**Forming door openings in partitions (NRM2 16 / package JOI)**											
	From the TLSTF door report (12 openings). Per opening: 2 full-height king studs, head at ~2,100, cripples over, bottom rail cut out. Timber in 5B.											
5C.1	Form door opening 726 wide x ~2,100 high in the 89 partition	nr		4.00		**4.00**			£0.00	£0.00	**£0.00**	Doorsets in Bill 3
5C.2	Form door opening 926 wide x ~2,100 high in the 89 partition	nr		8.00		**8.00**			£0.00	£0.00	**£0.00**	Doorsets in Bill 3
5D	**Head restraint, pattresses, acoustic and fixings (NRM2 16 / package JOI)**											
	Heads: Galv slotted partition head clip to the metal-web joist bottom chord / noggin (5 mm deflection gap) - CONFIRM product - TLSTF ceiling-noggin report: 128 clips, 64 noggins between the roof joists where a partition runs parallel to them (5 mm deflection gap). Pattresses: 116 pieces of 18 WBP ply in the stud bays on the wet-room faces (BCP_pattress, 150-1,950 above the base). Bottom rails fixed down through the 22 deck into the floor joists / noggins (floor designer).											
5D.1	Slotted deflection head clip, galvanised, partition head rail to the PS10 bottom chord / noggin (product to confirm)	nr		128.00		**128.00**			£0.00	£0.00	**£0.00**	TLSTF ceiling-noggin report
5D.2	47 x 97 C24 ceiling noggins between the roof joists over the partitions running parallel to them (Z clips / hangers)	nr		64.00		**64.00**			£0.00	£0.00	**£0.00**	TLSTF ceiling-noggin report
5D.3	18 WBP ply pattress pieces in the stud bays (shower-room fittings, wall-hung sanitaryware)	nr		116.00		**116.00**			£0.00	£0.00	**£0.00**	BCP_pattress report
5D.4	Fix bottom rails through the 22 deck into the floor joists / noggins at max 600 c/c (+ floor noggins under partitions parallel to the joists - floor designer)	m		46.31		**46.31**			£0.00	£0.00	**£0.00**	Bottom rail length (door gaps excluded)

Ref	Description	Unit	FL 4F floor zone	L1 4F storey	RF Roof	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per zone FL / L1 / RF (Site total = sum of the zones)		**1**	**1**	**1**	**3**						Levels: FL = 4F floor zone: steel ring beam on the existing wall heads (~12,066) + transfers, the hung 4F floor (FFL 12,342) and the covered-terrace floor; L1 = the new 4F storey: Nudura 7 courses 12,320-15,520 (4 flats, the open-air stairwell, the covered terrace); RF = flat sedum roof on PS10 joists (finish ~15,401) + the covered-terrace roof
5D.5	Acoustic mineral wool quilt (min 10 kg/m3, 25 thick) in the partition voids - Part E E2 internal walls (Rw 40) round bedrooms / shower rooms	m2		141.78		**141.78**			£0.00	£0.00	**£0.00**	Allow all partitions
5D.6	Nails, screws, framing fixings and sundries for the partition framing	item							£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount.

PACKAGE SUMMARY - Bill 5 Timber Stud Partitions (TLSTF) - Framing, Openings, Head Restraint, Pattresses & Fixings (package JOI; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
5A	Timber stud partitions, non-loadbearing - framing (NRM2 16 / package JOI)	£0.00	£0.00	**£0.00**
5B	Partition timber - supply (NRM2 16 / package JOI)	£0.00	£0.00	**£0.00**
5C	Forming door openings in partitions (NRM2 16 / package JOI)	£0.00	£0.00	**£0.00**
5D	Head restraint, pattresses, acoustic and fixings (NRM2 16 / package JOI)	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 5, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the ICF package (distributor kit / BuildEase charges).

Bill 6 - Structure - Steel Ring Beam & Transfers, 4F Hung Floor, Covered-terrace Floor (coordination); Existing Building Excluded

Coordination quantities for the engineer / steel fabricator / floor designer: the indicative ring beam + transfers, the PS10 hung 4F floor and the covered-terrace floor. The existing building is excluded. [NRM2 14 / 16 / 18 / package STR / FLR]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the ICF package (the Nudura formwork and accessories supplied and priced by the distributor, and the BuildEase pre-cut service and delivery) and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer, fire engineer or supplier) before use. Quantities are measured from the BuildEase quotation model of the Huw Griffiths Architects planning drawings HG-24-02-05 / -06 rev 03 (October 2025, 1:100: proposed 4F plan, roof plan, elevations) and the existing drawings HG-24-02-02 / -03; no allowance for waste is included unless stated. Quantity columns are the zones FL (4F floor zone) / L1 (4F storey) / RF (roof); the Site total is their sum. The existing building is excluded. Rates and amounts are by others.

Ref	Description	Unit	FL 4F floor zone	L1 4F storey	RF Roof	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per zone FL / L1 / RF (Site total = sum of the zones)		**1**	**1**	**1**	**3**						Levels: FL = 4F floor zone: steel ring beam on the existing wall heads (~12,066) + transfers, the hung 4F floor (FFL 12,342) and the covered-terrace floor; L1 = the new 4F storey: Nudura 7 courses 12,320-15,520 (4 flats, the open-air stairwell, the covered terrace); RF = flat sedum roof on PS10 joists (finish ~15,401) + the covered-terrace roof
6A	**Steel ring beam, transfer steels and terrace edge beam (NRM2 14 - package STR; STRUCTURAL ENGINEER - INDICATIVE, by others)**											
	Indicative steels in cgf_steel.json (5,633.3 kg): the RING BEAM on the existing wall heads (top 12,320 = the ICF base), the TRANSFER beams under the 4F front wall, the two stair-core walls and the flat-separating walls, and the covered-terrace roof EDGE BEAM in pockets in the ICF returns. Sections, connections, bearings on the existing walls (structural survey of the walls and their foundations), fire and corrosion protection by the engineer. Ring beam + transfers INDICATIVE - structural engineer to design sections, connections, bearings on the existing walls.											
6A.1	RB1 UB 254x146x37 - ring beam on the existing (east) side wall head (INDICATIVE section)	m	24.86			**24.86**			£0.00	£0.00	**£0.00**	919.7 kg (model)
6A.2	RB2 UB 254x146x37 - ring beam on the existing (west, neighbour) side wall head (INDICATIVE section)	m	24.86			**24.86**			£0.00	£0.00	**£0.00**	919.7 kg (model)
6A.3	RB3 UB 254x146x37 - ring beam on the existing rear wall head (INDICATIVE section)	m	10.01			**10.01**			£0.00	£0.00	**£0.00**	370.3 kg (model)
6A.4	TB1 UB 406x178x60 - transfer under the 4f front (terrace) wall (INDICATIVE section)	m	10.01			**10.01**			£0.00	£0.00	**£0.00**	601.4 kg (model)
6A.5	TB2 UB 406x178x60 - transfer under stair-core wall a (INDICATIVE section)	m	10.01			**10.01**			£0.00	£0.00	**£0.00**	601.4 kg (model)
6A.6	TB3 UB 406x178x60 - transfer under stair-core wall b (INDICATIVE section)	m	10.01			**10.01**			£0.00	£0.00	**£0.00**	601.4 kg (model)
6A.7	TB4 UB 406x178x60 - transfer under the flat-separating wall a (INDICATIVE section)	m	9.12			**9.12**			£0.00	£0.00	**£0.00**	548.3 kg (model)
6A.8	TB5 UB 406x178x60 - transfer under the flat-separating wall b (INDICATIVE section)	m	9.17			**9.17**			£0.00	£0.00	**£0.00**	551.2 kg (model)
6A.9	TB6 UB 406x178x60 - terrace floor transfer on the separating-wall line (INDICATIVE section)	m	2.50			**2.50**			£0.00	£0.00	**£0.00**	150.0 kg (model)
6A.10	EB1 UB 254x146x37 - covered-terrace roof edge beam, 100 bearing in pockets in the icf returns (INDICATIVE section)	m			10.00	**10.00**			£0.00	£0.00	**£0.00**	369.9 kg (model)
6A.11	*Steel total weight (all ring / transfer / edge beams) - for information*	*kg*	*5,263.40*		*369.90*	*5,633.30*					*not priced*	*cgf_steel.json total_kg*
6A.12	Bearings / padstones / spreaders on the existing wall heads under the ring beam and the transfer ends, packers to level	nr	18.00			**18.00**			£0.00	£0.00	**£0.00**	2 per beam - PROVISIONAL, engineer
6A.13	Connections (ring-beam corners / splices, transfer-to-ring-beam end plates), holding-down to the existing walls	item	1.00			**1.00**			£0.00	£0.00	**£0.00**	Engineer
6A.14	Fire protection to the steels (intumescent / board, period per the fire strategy - flats, 11-18 m band)	m	110.54		10.00	**120.53**			£0.00	£0.00	**£0.00**	Fire engineer
6A.15	Structural survey of the existing walls / foundations, temporary works, propping and weather protection of the existing building during the works	item							£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount. Engineer / contractor - PROVISIONAL
6B	**4F hung floor - PS10 metal-web joists hung from the steels (NRM2 16 - package FLR; floor designer / engineer, by others)**											
	As modelled (cgf_floor_4F.json): 114 PS10 metal-web joists (12,067-12,320) hung from the ring beam and the transfer steels on a timber packer / ledger bolted in the steel web (12,095-12,273), 22 deck (FFL 12,342), 6 bays (flats 179.21 m2 + the covered-terrace floor 24.41 m2 = 203.62 m2). The floor is over the existing 3F flats / roof: a SEPARATING floor (Part E + compartment floor, ADB Wales) - acoustician / fire engineer.											
6B.1	PS10 metal-web joists (bays FA1 24, FA2 24, FB1 24, FB2 24, FT1 9, FT2 9)	nr	114.00			**114.00**			£0.00	£0.00	**£0.00**	
6B.2	Joist hangers / bearings at the steels (2 per joist)	nr	228.00			**228.00**			£0.00	£0.00	**£0.00**	
6B.3	Timber packer / ledger bolted in the steel web at the joist ends (both ends of each bay)	m	82.97			**82.97**			£0.00	£0.00	**£0.00**	

Ref	Description	Unit	FL 4F floor zone	L1 4F storey	RF Roof	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per zone FL / L1 / RF (Site total = sum of the zones)		1	1	1	3						Levels: FL = 4F floor zone: steel ring beam on the existing wall heads (~12,066) + transfers, the hung 4F floor (FFL 12,342) and the covered-terrace floor; L1 = the new 4F storey: Nudura 7 courses 12,320-15,520 (4 flats, the open-air stairwell, the covered terrace); RF = flat sedum roof on PS10 joists (finish ~15,401) + the covered-terrace roof
6B.4	Strongbacks (one run per bay)	m	41.48			**41.48**			£0.00	£0.00	**£0.00**	
6B.5	22 flooring-grade deck, glued and screwed (186 boards)	m2	203.62			**203.62**			£0.00	£0.00	**£0.00**	
6B.6	Acoustic / thermal insulation between the joists over the existing building (separating floor) - PROVISIONAL	m2	179.21			**179.21**			£0.00	£0.00	**£0.00**	
6B.7	Resilient layer / floating floor or resilient ceiling to the separating floor (Part E - acoustician) - PROVISIONAL	m2	179.21			**179.21**			£0.00	£0.00	**£0.00**	
6B.8	Fire-stopping / cavity closers at the floor perimeter and round the steels (compartment floor)	m	110.02			**110.02**			£0.00	£0.00	**£0.00**	
6C	**Covered terrace floor (NRM2 18 - package FLR / RFC; by others)**											
	The covered terrace in front of the flats (bays FT1 / FT2, 24.41 m2 on the hung floor, X 0-2,407): open-sided under the terrace roof - waterproofing, falls, drainage and the threshold coordination with the terrace doors F01 / F02 (Part M level access).											
6C.1	Terrace deck waterproofing (membrane on the deck, falls / firrings, upstands to the ICF and the door thresholds)	m2	24.41			**24.41**			£0.00	£0.00	**£0.00**	PROVISIONAL
6C.2	Terrace finish: paving on pedestals / external decking over the membrane	m2	24.41			**24.41**			£0.00	£0.00	**£0.00**	PROVISIONAL
6C.3	Terrace drainage outlet / channel + rainwater connection	nr	2.00			**2.00**			£0.00	£0.00	**£0.00**	PROVISIONAL
6D	**Existing building - EXCLUDED (not measured)**											
6D.1	ALL works to the existing GF-3F masonry building - structure, the existing roof (strip-out / make good / retain under the new floor), the existing common stair below 4F, services, the existing cladding / render, party-wall works - NOT in this package	item							£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount. EXCLUDED - by others

PACKAGE SUMMARY - Bill 6 Structure - Steel Ring Beam & Transfers, 4F Hung Floor, Covered-terrace Floor (coordination); Existing Building Excluded (package STR / FLR; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
6A	Steel ring beam, transfer steels and terrace edge beam (NRM2 14 - package STR; STRUCTURAL ENGINEER - INDICATIVE, by others)	£0.00	£0.00	**£0.00**
6B	4F hung floor - PS10 metal-web joists hung from the steels (NRM2 16 - package FLR; floor designer / engineer, by others)	£0.00	£0.00	**£0.00**
6C	Covered terrace floor (NRM2 18 - package FLR / RFC; by others)	£0.00	£0.00	**£0.00**
6D	Existing building - EXCLUDED (not measured)	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 6, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the ICF package (distributor kit / BuildEase charges).

Bill 7 - Flat Sedum Roof - PS10 Joists, Warm-roof Build-up, Upstands, Wall-head Capping, Outlets & Terrace Soffit

The flat sedum / wildflower roof on PS10 metal-web joists between the ICF walls, the warm-roof build-up, upstands, wall-head capping, outlets, the covered-terrace roof edge and soffit. [NRM2 16 / 18 / package RFS / RFC]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the ICF package (the Nudura formwork and accessories supplied and priced by the distributor, and the BuildEase pre-cut service and delivery) and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer, fire engineer or supplier) before use. Quantities are measured from the BuildEase quotation model of the Huw Griffiths Architects planning drawings HG-24-02-05 / -06 rev 03 (October 2025, 1:100: proposed 4F plan, roof plan, elevations) and the existing drawings HG-24-02-02 / -03; no allowance for waste is included unless stated. Quantity columns are the zones FL (4F floor zone) / L1 (4F storey) / RF (roof); the Site total is their sum. The existing building is excluded. Rates and amounts are by others.

Ref	Description	Unit	FL 4F floor zone	L1 4F storey	RF Roof	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per zone FL / L1 / RF (Site total = sum of the zones)		1	1	1	3						Levels: FL = 4F floor zone: steel ring beam on the existing wall heads (~12,066) + transfers, the hung 4F floor (FFL 12,342) and the covered-terrace floor; L1 = the new 4F storey: Nudura 7 courses 12,320-15,520 (4 flats, the open-air stairwell, the covered terrace); RF = flat sedum roof on PS10 joists (finish ~15,401) + the covered-terrace roof
7A Roof structure - PS10 metal-web joists on the ICF walls (NRM2 16 - package RFS; roof designer / engineer)												
	As modelled (cgf_floor_RF.json): 117 PS10 metal-web joists (14,846-15,099) spanning between the ICF walls on ledgers bolted to the ICF (14,874-15,052); the covered-terrace roof bay RT spans from the edge beam EB1 to the flats' front wall. 5 bays, 193.28 m2. The ICF walls (incl. the internal core / separating walls) rise to 15,520.4, 119 above the finished sedum (15,401) - the roof is split into bays by the wall heads.											
7A.1	PS10 metal-web roof joists (bays RA1 23, RA2 23, RB1 23, RB2 23, RT 25)	nr			117.00	**117.00**			£0.00	£0.00	**£0.00**	
7A.2	Joist hangers / bearings (2 per joist)	nr			234.00	**234.00**			£0.00	£0.00	**£0.00**	
7A.3	Timber ledger resin-anchored / bolted to the ICF wall faces at the joist ends (fixings into the cured core, engineer)	m			81.77	**81.77**			£0.00	£0.00	**£0.00**	
7A.4	Timber packer in the edge-beam web at the terrace roof joist ends	m			9.80	**9.80**			£0.00	£0.00	**£0.00**	
7A.5	Strongbacks (one run per flat bay)	m			35.99	**35.99**			£0.00	£0.00	**£0.00**	
7A.6	22 roof deck (OSB3 / ply - spec TBC, 172 boards)	m2			193.28	**193.28**			£0.00	£0.00	**£0.00**	
7B Roof coverings - warm flat roof with sedum / wildflower (NRM2 18 - package RFC; roofing / green-roof specialist)												
	Build-up as modelled: 22 deck + VCL + 180 PIR + membrane + 100 sedum (sedum + wildflower roof as the planning plan). Falls are NOT modelled (tapered insulation / firrings to the outlets - allow). PARAPET: the ICF tops are only 119 above the finished roof - a membrane upstand needs min 150 (BS 6229 / the membrane manufacturer): RFI (raise the ICF / lower the build-up / a kerb on the wall heads).											
7B.1	Vapour control layer on the deck, lapped and sealed, turned up at the walls	m2			193.28	**193.28**			£0.00	£0.00	**£0.00**	Order guide +10% = 212.6
7B.2	180 PIR roof insulation (+ tapered scheme for falls - PROVISIONAL)	m2			193.28	**193.28**			£0.00	£0.00	**£0.00**	Order guide +5% = 202.9
7B.3	Single-ply / bituminous waterproofing membrane with root-resistant cap (green-roof rated)	m2			193.28	**193.28**			£0.00	£0.00	**£0.00**	Order guide +10% = 212.6
7B.4	Sedum / wildflower green-roof system 100: drainage / water-retention layer, filter fleece, substrate, sedum blanket / plug planting	m2			193.28	**193.28**			£0.00	£0.00	**£0.00**	Less the vegetation-free zones (7B.6)
7B.5	Membrane upstands to the ICF wall heads round every roof bay (terrace roof: 3 sides), with termination / counter-flashing	m			124.34	**124.34**			£0.00	£0.00	**£0.00**	Bay perimeters (cgf_floor_RF bays)
7B.6	Vegetation-free zone 300-500 wide (pebble / paving) round every bay perimeter and the outlets	m			124.34	**124.34**			£0.00	£0.00	**£0.00**	Bay perimeters
7B.7	Wall-head capping / coping (PPC aluminium or precast - spec TBC) over every ICF wall top (envelope + core + separating walls)	m			107.96	**107.96**			£0.00	£0.00	**£0.00**	Wall centre lines (bom_finish core_lengths_m)
7B.8	Roof outlets (1 per bay) + overflow / spitter through the parapet (1 per bay), leaf guards	nr			10.00	**10.00**			£0.00	£0.00	**£0.00**	PROVISIONAL - drainage design
7B.9	Rainwater pipes from the roof outlets down the building to the drainage (internal / external route - TBC)	item							£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount. PROVISIONAL
7B.10	Covered-terrace roof front edge on the edge beam EB1: edge trim, gutter, fascia / soffit cladding to the beam	m			9.80	**9.80**			£0.00	£0.00	**£0.00**	RT bay front edge
7B.11	Edge protection / fall-arrest system for roof maintenance (parapet only ~120 above the roof) + roof access (hatch / ladder) - PROVISIONAL	item							£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount. Not drawn - CDM / maintenance strategy
7C Covered-terrace soffit (NRM2 18 / 28 - package RFC / EXT)												

Ref	Description	Unit	FL 4F floor zone	L1 4F storey	RF Roof	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per zone FL / L1 / RF (Site total = sum of the zones)		**1**	**1**	**1**	**3**						Levels: FL = 4F floor zone: steel ring beam on the existing wall heads (~12,066) + transfers, the hung 4F floor (FFL 12,342) and the covered-terrace floor; L1 = the new 4F storey: Nudura 7 courses 12,320-15,520 (4 flats, the open-air stairwell, the covered terrace); RF = flat sedum roof on PS10 joists (finish ~15,401) + the covered-terrace roof
7C.1	External-grade soffit lining under the terrace roof joists (cement board / cladding - as the architect), incl. ventilation / trims	m2			22.12	**22.12**			£0.00	£0.00	**£0.00**	RT bay 22.12 m2
7C.2	Fire stopping / cavity closers at the ICF wall heads under the roof deck and round the steel edge beam (compartment walls, ADB Wales)	item							£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount.

PACKAGE SUMMARY - Bill 7 Flat Sedum Roof - PS10 Joists, Warm-roof Build-up, Upstands, Wall-head Capping, Outlets & Terrace Soffit (package RFS / RFC; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
7A	Roof structure - PS10 metal-web joists on the ICF walls (NRM2 16 - package RFS; roof designer / engineer)	£0.00	£0.00	**£0.00**
7B	Roof coverings - warm flat roof with sedum / wildflower (NRM2 18 - package RFC; roofing / green-roof specialist)	£0.00	£0.00	**£0.00**
7C	Covered-terrace soffit (NRM2 18 / 28 - package RFC / EXT)	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 7, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the ICF package (distributor kit / BuildEase charges).

Bill 8 - Opening Schedule - Lift-and-slide Doors, Flat Entrance Doors, Windows; Terrace & Juliet Balustrades

One line per opening unit (with its cill, tapes, fixings, locks) from the BuildEase window fit; the covered-terrace balustrade, the rear Juliet balustrades and the fire-glazing check. [NRM2 25 / package WIN / MET]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the ICF package (the Nudura formwork and accessories supplied and priced by the distributor, and the BuildEase pre-cut service and delivery) and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer, fire engineer or supplier) before use. Quantities are measured from the BuildEase quotation model of the Huw Griffiths Architects planning drawings HG-24-02-05 / -06 rev 03 (October 2025, 1:100: proposed 4F plan, roof plan, elevations) and the existing drawings HG-24-02-02 / -03; no allowance for waste is included unless stated. Quantity columns are the zones FL (4F floor zone) / L1 (4F storey) / RF (roof); the Site total is their sum. The existing building is excluded. Rates and amounts are by others.

Ref	Description	Unit	FL 4F floor zone	L1 4F storey	RF Roof	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per zone FL / L1 / RF (Site total = sum of the zones)		**1**	**1**	**1**	**3**						Levels: FL = 4F floor zone: steel ring beam on the existing wall heads (~12,066) + transfers, the hung 4F floor (FFL 12,342) and the covered-terrace floor; L1 = the new 4F storey: Nudura 7 courses 12,320-15,520 (4 flats, the open-air stairwell, the covered terrace); RF = flat sedum roof on PS10 joists (finish ~15,401) + the covered-terrace roof
8A	**Opening schedule - one line per unit incl. accessories (NRM2 25 - package WIN; window / door supplier)**											
	From the BuildEase window fit (bcw_fit.json, 12 units): structural opening (so) sizes, frames tight to the back of the outer EPS. One line per unit so that each can be priced as supplied + fitted with its accessories. The windows and flat entrance doors open onto the OPEN-AIR STAIRWELL (the escape route): fire-resisting glazing / doors and self-closing per the fire engineer (ADB vol 1 Wales) - see 8C.											
8A.1	CAD1: composite door (48 slab, multi-point lock, vision panel), 901 x 2,101 so, onto the open-air stairwell; incl. cill (180), lever / multi-point lock, door viewer, self-closer IF the fire strategy requires, internal airtight tape, frame fixings into the ICF, sealant	nr		1.00		**1.00**			£0.00	£0.00	**£0.00**	spec 900 x 2,100, sill 0; PAS 24 security
8A.2	CAD2: composite door (48 slab, multi-point lock, vision panel), 901 x 2,101 so, onto the open-air stairwell; incl. cill (180), lever / multi-point lock, door viewer, self-closer IF the fire strategy requires, internal airtight tape, frame fixings into the ICF, sealant	nr		1.00		**1.00**			£0.00	£0.00	**£0.00**	spec 900 x 2,100, sill 0; PAS 24 security
8A.3	CBD1: composite door (48 slab, multi-point lock, vision panel), 901 x 2,101 so, onto the open-air stairwell; incl. cill (180), lever / multi-point lock, door viewer, self-closer IF the fire strategy requires, internal airtight tape, frame fixings into the ICF, sealant	nr		1.00		**1.00**			£0.00	£0.00	**£0.00**	spec 900 x 2,100, sill 0; PAS 24 security
8A.4	CBD2: composite door (48 slab, multi-point lock, vision panel), 901 x 2,101 so, onto the open-air stairwell; incl. cill (180), lever / multi-point lock, door viewer, self-closer IF the fire strategy requires, internal airtight tape, frame fixings into the ICF, sealant	nr		1.00		**1.00**			£0.00	£0.00	**£0.00**	spec 900 x 2,100, sill 0; PAS 24 security
8A.5	F01: Aluminium lift-and-slide / glazed doors (PPC RAL 7016, low threshold), 2,651 x 2,501 so, onto the covered terrace; incl. PPC aluminium cill (225), low threshold, multi-point locking, internal airtight tape (illbruck ME110 or equal), DPC tray, frame fixings into the ICF, frame sealant	nr		1.00		**1.00**			£0.00	£0.00	**£0.00**	spec 2,650 x 2,500, sill 0; PAS 24 security
8A.6	F02: Aluminium lift-and-slide / glazed doors (PPC RAL 7016, low threshold), 2,651 x 2,501 so, onto the covered terrace; incl. PPC aluminium cill (225), low threshold, multi-point locking, internal airtight tape (illbruck ME110 or equal), DPC tray, frame fixings into the ICF, frame sealant	nr		1.00		**1.00**			£0.00	£0.00	**£0.00**	spec 2,650 x 2,500, sill 0; PAS 24 security
8A.7	R01: Aluminium lift-and-slide / glazed doors (PPC RAL 7016, low threshold), 2,651 x 2,501 so, rear elevation (onto a Juliet balustrade - 8B.2); incl. PPC aluminium cill (225), low threshold, multi-point locking, internal airtight tape (illbruck ME110 or equal), DPC tray, frame fixings into the ICF, frame sealant	nr		1.00		**1.00**			£0.00	£0.00	**£0.00**	spec 2,650 x 2,500, sill 0; PAS 24 security

Ref	Description	Unit	FL 4F floor zone	L1 4F storey	RF Roof	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per zone FL / L1 / RF (Site total = sum of the zones)		1	1	1	3						Levels: FL = 4F floor zone: steel ring beam on the existing wall heads (~12,066) + transfers, the hung 4F floor (FFL 12,342) and the covered-terrace floor; L1 = the new 4F storey: Nudura 7 courses 12,320-15,520 (4 flats, the open-air stairwell, the covered terrace); RF = flat sedum roof on PS10 joists (finish ~15,401) + the covered-terrace roof
8A.8	R02: Aluminium lift-and-slide / glazed doors (PPC RAL 7016, low threshold), 2,651 x 2,501 so, rear elevation (onto a Juliet balustrade - 8B.2); incl. PPC aluminium cill (225), low threshold, multi-point locking, internal airtight tape (illbruck ME110 or equal), DPC tray, frame fixings into the ICF, frame sealant	nr		1.00		**1.00**			£0.00	£0.00	**£0.00**	spec 2,650 x 2,500, sill 0; PAS 24 security
8A.9	CAW1: Alu-clad casement window (RAL 7016), 3 lights (2 opening), 1,751 x 1,201 so, onto the open-air stairwell; incl. PPC aluminium cill (180), restrictors, trickle vent, internal airtight tape, DPC tray, frame fixings into the ICF, sealant	nr		1.00		**1.00**			£0.00	£0.00	**£0.00**	spec 1,750 x 1,200, sill 900; PAS 24 security
8A.10	CAW2: Alu-clad casement window (RAL 7016), 3 lights (2 opening), 1,751 x 1,201 so, onto the open-air stairwell; incl. PPC aluminium cill (180), restrictors, trickle vent, internal airtight tape, DPC tray, frame fixings into the ICF, sealant	nr		1.00		**1.00**			£0.00	£0.00	**£0.00**	spec 1,750 x 1,200, sill 900; PAS 24 security
8A.11	CBW1: Alu-clad casement window (RAL 7016), 3 lights (2 opening), 1,751 x 1,201 so, onto the open-air stairwell; incl. PPC aluminium cill (180), restrictors, trickle vent, internal airtight tape, DPC tray, frame fixings into the ICF, sealant	nr		1.00		**1.00**			£0.00	£0.00	**£0.00**	spec 1,750 x 1,200, sill 900; PAS 24 security
8A.12	CBW2: Alu-clad casement window (RAL 7016), 3 lights (2 opening), 1,751 x 1,201 so, onto the open-air stairwell; incl. PPC aluminium cill (180), restrictors, trickle vent, internal airtight tape, DPC tray, frame fixings into the ICF, sealant	nr		1.00		**1.00**			£0.00	£0.00	**£0.00**	spec 1,750 x 1,200, sill 900; PAS 24 security
8A.T	**Opening schedule - total units**	**nr**		**12.00**		**12.00**					*not priced*	
8B	**Balustrades and guarding (NRM2 25 / 22 - package MET)**											
8B.1	Covered-terrace edge balustrade: terrace edge 1,100 glass (frameless glass in a base shoe on the floor edge / steel - spec TBC)	m	9.80			**9.80**			£0.00	£0.00	**£0.00**	cgf_floor_4F extra (terrace edge)
8B.2	Juliet balustrade 1,100 (glass / steel, fixed into the ICF reveals) to the rear lift-and-slide doors (sill 0 at 4F, no balcony drawn)	nr		2.00		**2.00**			£0.00	£0.00	**£0.00**	L1-R01, L1-R02 - PROVISIONAL, check the rear elevation
8C	**Items not modelled (PROVISIONAL)**											
8C.1	Fire-resisting (integrity) glazing / fixed lights to the bedroom windows facing the open-air escape stair and fire-rated flat entrance doorsets - extra over 8A IF the fire strategy requires	nr		8.00		**8.00**			£0.00	£0.00	**£0.00**	Fire engineer / building control (ADB vol 1 Wales)
8C.2	Background ventilators / MVHR strategy (Approved Document F Wales) and the overheating check (Approved Document O Wales) - window supplier / M&E	nr		12.00		**12.00**			£0.00	£0.00	**£0.00**	One per unit - PROVISIONAL

PACKAGE SUMMARY - Bill 8 Opening Schedule - Lift-and-slide Doors, Flat Entrance Doors, Windows; Terrace & Juliet Balustrades (package WIN / MET; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
8A	Opening schedule - one line per unit incl. accessories (NRM2 25 - package WIN; window / door supplier)	£0.00	£0.00	**£0.00**
8B	Balustrades and guarding (NRM2 25 / 22 - package MET)	£0.00	£0.00	**£0.00**
8C	Items not modelled (PROVISIONAL)	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 8, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the ICF package (distributor kit / BuildEase charges).

Schedule A - Areas: External Faces, Lining Zones, Flats,

ICF face areas by elevation / zone (component export), flat / floor / roof areas (CG_spec din

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the ICF package (the Nudura formwork and accessories supplied and priced by the distributor, and the BuildEase pre-cut service and delivery) and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer, fire engineer or supplier) before use. Quantities are measured from the BuildEase quotation model of the Huw Griffiths Architects planning drawings HG-24-02-05 / -06 rev 03 (October 2025, 1:100: proposed 4F plan, roof plan, elevations) and the existing drawings HG-24-02-02 / -03; no allowance for waste is included unless stated. Quantity columns are the zones FL (4F floor zone) / L1 (4F storey) / RF (roof); the Site total is their sum. The existing building is excluded. Rates and amounts are by others.

Zone	Item	Source	Length m	Depth / width m	Area m2
L1	East side elevation, ICF outer faces	CG_components.json	24.86		76.80
L1	West side (against the neighbour), ICF outer faces	components	24.86		76.62
L1	Rear elevation incl. corners, ICF outer faces (net)	components	10.51		26.44
L1	Covered terrace - flats' front wall outer face (net)	components	9.80		18.48
L1	Covered terrace - return inner faces + return ends	components + ends	4.81		17.53
L1	Open-air stairwell - core-wall faces (net)	components			46.96
L1	Open-air stairwell - side-wall inner faces	components	6.35		19.53
L1	ICF faces in the lining zone - envelope (flats)	components		2.50	111.95
L1	ICF faces in the lining zone - core walls, flat side	components		2.50	33.44
L1	ICF faces in the lining zone - separating walls, both faces	components		2.50	90.11
L1	Flat A1 floor area between the ICF faces	CG_spec dims	27.75		43.96
L1	Flat A2 floor area between the ICF faces	CG_spec dims	27.20		41.47
L1	Flat B1 floor area between the ICF faces	CG_spec dims	27.82		44.12
L1	Flat B2 floor area between the ICF faces	CG_spec dims	27.26		41.61
L1	Stairwell (open to atmosphere) between the core walls	CG_spec dims			31.10
L1	Covered terrace (plan, X 0 to the flats' front wall)	CG_spec dims	9.80	2.41	23.58
FL	4F hung floor - flat bays (FA / FB)	cgf_floor_4F.json			179.21
FL	4F hung floor - covered-terrace bays (FT)	cgf_floor_4F.json			24.41
FL	Floor-zone band over the ring beam (east + rear)	derived	35.37	0.25	8.98
RF	Roof bays (RA / RB flats + RT terrace)	cgf_floor_RF.json	124.34		193.28
RF	Covered-terrace roof bay RT (soffit)	cgf_floor_RF.json	9.80		22.12
L1	Flat ceilings (flat areas less the partition footprints)	derived			164.71

The stairwell is open to atmosphere: its faces are external. The west side faces the taller neighbour (exposed area TBC).

Schedule B - Openings Schedule (spec openings + BuildEase window fit)

From CG_spec.json (12 ICF openings) and bcw_fit.json (12 fitted units). Not priced.

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the ICF package (the Nudura formwork and accessories supplied and priced by the distributor, and the BuildEase pre-cut service and delivery) and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer, fire engineer or supplier) before use. Quantities are measured from the BuildEase quotation model of the Huw Griffiths Architects planning drawings HG-24-02-05 / -06 rev 03 (October 2025, 1:100: proposed 4F plan, roof plan, elevations) and the existing drawings HG-24-02-02 / -03; no allowance for waste is included unless stated. Quantity columns are the zones FL (4F floor zone) / L1 (4F storey) / RF (roof); the Site total is their sum. The existing building is excluded. Rates and amounts are by others.

Ref	Type	Fit style	Onto	W mm	H mm	Sill mm	Area m2	Fit so (W x H)	Source
L1-F01	door	double_door	terrace	2650	2500	0	6.62	2651 x 2501	plan gap 1414-4064 / 672
L1-R01	door	double_door	rear	2650	2500	0	6.62	2651 x 2501	plan gap 1414-4064 / 672
L1-F02	door	double_door	terrace	2650	2500	0	6.62	2651 x 2501	plan gap 1414-4064 / 672
L1-R02	door	double_door	rear	2650	2500	0	6.62	2651 x 2501	plan gap 1414-4064 / 672
L1-CAD1	door	composite_door	stair	900	2100	0	1.89	901 x 2101	plan gap 504-1403 shifte
L1-CAD2	door	composite_door	stair	900	2100	0	1.89	901 x 2101	plan gap 9383-10283 shif
L1-CAW1	window	window	stair	1750	1200	900	2.10	1751 x 1201	plan gap 2978-4729
L1-CAW2	window	window	stair	1750	1200	900	2.10	1751 x 1201	plan gap 6058-7808
L1-CBD1	door	composite_door	stair	900	2100	0	1.89	901 x 2101	plan gap 504-1403 shifte
L1-CBD2	door	composite_door	stair	900	2100	0	1.89	901 x 2101	plan gap 9383-10283 shif
L1-CBW1	window	window	stair	1750	1200	900	2.10	1751 x 1201	plan gap 2978-4729
L1-CBW2	window	window	stair	1750	1200	900	2.10	1751 x 1201	plan gap 6058-7808

Heights / sills relative to the ICF base. Front (terrace) and rear lift-and-slide doors in the XR35 walls; flat entrance doors and bedroom windows in the 6in Standard core walls onto the stairwell.

Schedule C - Key Quantities per Flat

Reference only - the bills carry the priced quantities. Not priced.

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the ICF package (the Nudura formwork and accessories supplied and priced by the distributor, and the BuildEase pre-cut service and delivery) and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer, fire engineer or supplier) before use. Quantities are measured from the BuildEase quotation model of the Huw Griffiths Architects planning drawings HG-24-02-05 / -06 rev 03 (October 2025, 1:100: proposed 4F plan, roof plan, elevations) and the existing drawings HG-24-02-02 / -03; no allowance for waste is included unless stated. Quantity columns are the zones FL (4F floor zone) / L1 (4F storey) / RF (roof); the Site total is their sum. The existing building is excluded. Rates and amounts are by others.

Flat	Floor area m2	Perimeter m	Partitions nr	Partitions m	Doors nr	Pattress pieces	Head clips
A1	43.96	27.75	6	14.16	3	30	32
A2	41.47	27.20	6	14.16	3	28	32
B1	44.12	27.82	6	14.16	3	30	32
B2	41.61	27.26	6	14.16	3	28	32
Total	**171.16**	**110.03**	**24.00**	**56.64**	**12.00**	**116.00**	**128.00**

Flat areas between the ICF inner faces (CG_spec dims); partitions / doors / pattresses / clips from the TLSTF reports.

Schedule D - TLSTF Partition Schedule (as built in the model)

From the TLSTF walls / verify / doors / ceiling-noggin reports (04_Logs/build/BCP_*). Not priced.

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the ICF package (the Nudura formwork and accessories supplied and priced by the distributor, and the BuildEase pre-cut service and delivery) and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer, fire engineer or supplier) before use. Quantities are measured from the BuildEase quotation model of the Huw Griffiths Architects planning drawings HG-24-02-05 / -06 rev 03 (October 2025, 1:100: proposed 4F plan, roof plan, elevations) and the existing drawings HG-24-02-02 / -03; no allowance for waste is included unless stated. Quantity columns are the zones FL (4F floor zone) / L1 (4F storey) / RF (roof); the Site total is their sum. The existing building is excluded. Rates and amounts are by others.

Floor	Wall	Length mm	Height mm	Area m2	Build-up	Studs	Members	Door openings (mm)	Head clips
4F	A2-P01	3538	2,504	8.86	bc_int_89_400 (wet)	10	42		7
4F	A2-P02	3538	2,504	8.86	bc_int_89_400 (wet)	9	48	926	6
4F	A2-P03	1542	2,504	3.86	bc_int_89_400 (wet)	6	30	726	4
4F	A2-P04	1720	2,504	4.31	bc_int_89_600	4	15		4
4F	A2-P05	3068	2,504	7.68	bc_int_89_600	7	37	926	8
4F	A2-P06	751	2,504	1.88	bc_int_89_600	3	11		3
4F	A1-P01	3538	2,504	8.86	bc_int_89_400 (wet)	11	46		7
4F	A1-P02	3538	2,504	8.86	bc_int_89_400 (wet)	10	52	926	6
4F	A1-P03	1542	2,504	3.86	bc_int_89_400 (wet)	6	30	726	4
4F	A1-P04	1720	2,504	4.31	bc_int_89_600	4	15		4
4F	A1-P05	3068	2,504	7.68	bc_int_89_600	7	37	926	8
4F	A1-P06	751	2,504	1.88	bc_int_89_600	3	11		3
4F	B2-P01	3538	2,504	8.86	bc_int_89_400 (wet)	10	42		7
4F	B2-P02	3538	2,504	8.86	bc_int_89_400 (wet)	9	48	926	6
4F	B2-P03	1542	2,504	3.86	bc_int_89_400 (wet)	5	28	726	4
4F	B2-P04	1720	2,504	4.31	bc_int_89_600	5	19		4
4F	B2-P05	3068	2,504	7.68	bc_int_89_600	8	41	926	8
4F	B2-P06	751	2,504	1.88	bc_int_89_600	3	11		3
4F	B1-P01	3538	2,504	8.86	bc_int_89_400 (wet)	11	46		7
4F	B1-P02	3538	2,504	8.86	bc_int_89_400 (wet)	10	52	926	6
4F	B1-P03	1542	2,504	3.86	bc_int_89_400 (wet)	5	28	726	4

Floor	Wall	Length mm	Height mm	Area m2	Build-up	Studs	Members	Door openings (mm)	Head clips
4F	B1-P04	1720	2,504	4.31	bc_int_89_600	5	19		4
4F	B1-P05	3068	2,504	7.68	bc_int_89_600	8	41	926	8
4F	B1-P06	751	2,504	1.88	bc_int_89_600	3	11		3

4F 24 walls 56.6 m x 2,504 (12 wet-room walls), 12 door openings. Height: 4F FFL to 5 mm under the roof-joist bottom chord.